जयपुर विकास प्राधिकरण,जयपुर

कुमांक:- जविप्रा / अधि.अभि.(उद्यान) / 2015 / डी- 32 7

दिनांकः 3, 8, २७।४

संशोधित निविदा सूचना

बिड सूचना अधि.अभि.(उद्यान) / 01 / 2015—16 ''खातीपुरा ग्रास फार्म नर्सरी, जियपुर का विकास'' जो निविदा सूचना क्रमांक डी—515 दिनांक 28.07.2015 के द्वारा जारी की गई थी, के Annexure: 2 अन्तर्गत प्रकाशित Estimated Procurement Cost INR Rs. 46,58,364.00 के स्थान पर 4479196.00 तथा Bid Security Deposit Amount (INR) : 2% (Rs. 93167/- के स्थान पर Rs. 89584/-) तथा 0.5% (Rs. 23292/- के स्थान पर Rs. 22396/-) पढ़ा जावे। निविदा की शेष शर्ते यथावत रहेगी।

अधिशाषी अभियन्ता (उद्यान) ० ८ जविप्रा, जयपुर।

प्रतिलिपि:-

विशेषाधिकारी जनसम्पर्क, जिवप्रा, जयपुर को प्रकाशन हेतु प्रेषित है।
 (जोब नं. 317 / 2014–15)

अधिशाषी अभियन्ता (उद्यान) ० ८ जविप्रा, जयपुर।

जयपुर विकास प्राधिकरण हिन्ना पुटिन जुवहरतिन नेहलनार्ग, जवपुर-302804

क्रमांक: जविधा/दांध अपि (उद्या)/2015/दी-527 दिनांक: — 3.8.2015
स्रिशोधित निविदा सूचना
विड ३६वना अधि अपि (उद्यान)/01/2015-16 "खारीपुण यास फार्म नर्सरी, जिया आपि अपि (उद्यान)/01/2015-16 "खारीपुण यास फार्म नर्सरी, जिया आपि अपि मई भी के Annexure: 2 अन्तर्गत प्रजाशित Estimated Frocurement Cost. INC Rs. 46,563.34.00 के स्थान पर 147714.3.00 तथा Bid Security Deposit Amount (INR): 2% (Rs. 831674- के स्थान पर Rs. 08584/-) तथा 0.5% (Rs. 23252/- के स्थान पर Rs. 22396/-) पढ़ा जावे। निविदा की शेष शर्ते प्रधात रहेगी।

राज,संवाद/सी/15/2310

अधिशाषी अमियन्ता (उद्यान)

दैनिक नवज्योति

JAIPUR DEVELOPMENT AUTHORIT
Room No. 234, Main Building, Ram Kishore Vyas Bhavan,
Indira Circle, Jawaharfal Nehru Marg, Jaipur-302 004
Telaphone 491-441-2555595 e-mail: xxxxxxxx@jaipurjda.org

VEX. DEVELOPINE N. AUTHORIE

WEX. DEVELOPE PRIV. 2015-16/D-212

NOTICE INVITING BID

NIB No.: EE-(Elect. PRNV13/2015-16

Bids are invited up-to 66.00 PM of 25.08.2015 for 33KV Charging Feedable Housing Schemes in JDA region, Jaipur. Dotalls may be seen in

Document at our office or the Notice of the Processing Processing Schemes in JDA region, Jaipur. Dotalls may be seen in

द हिन्दू दिनांक_ ... पृष्ते मं/८

7-8-15

JAIPUR DEVELOPMENT AUTHORIT


Room No. 234, Main Building, Ram Kishore Vyas Bhavan,
Indira Circle, Jawaharial Nehre Marg, Jaipur-302 004

Telephone +91-141-2569696 e-mail: xxxxxxxx@jaipurjda.org

दैनिक राष्ट्रदूत दिनांक पृष्ठ सं, 7 7 - 8 - 1 J

जलते दीप

पलत द्वाप दिनांक पुत्र संख्या <u>६</u> ७ - ८ - ७



जयपुर विकास प्राधिकरण इन्दर्स सर्वेत बवाहरतात शेहक गाँग, व्ययपुर-302004

/ब्रधि.अमि (उद्यान)/2015/डी-527 संशोधित निविदा सूचना

सिर्गाधित निविदा सूचना

बिड सुचना अधि.अमि. (उद्यान)/01/2015—16 "खातीपुरा ग्रास फार्म मसेरी.
जविधा, जन्दर का विकास" जो निरिदा सूचना क्रमांक डी-515 दिनांक 28.07.2015
के द्वारा जारी की गई थी.- के Annexure: 2 अन्तर्गत प्रकाशित Estimated
Procurement Cost INR Rs., 46,58,364.00 के स्थान पर 4479195.00 तथा, Bid
Procurement (INR): 2% (उ. 93187/- के स्थान पर Rs. 89584/-)-तथा
0.5% (Rs. 23292/- के स्थान पर Rs. 22396/-) पदा जावे। निविदा की शेष शर्त
थ्यावत रहेनी।
अधिशाधी अभियन्ता (प्रशासात संबद (सी)/15/2310

JAHUR DEVELOPMENT AUTHORITY

r/Elect-PRIV2015-16/D-212

NOTICE INVITING BID
NIB No.: EE-(Elect.-PRNY13/2015-16
ted up-to 96.00 PM of 25.08.2015 for 33KV CI
g Schemes in JBA region, Jaipur. Details ma
our office or the website of State Public Pro



JAIPUR DEVELOPMENT AUTHORITY, JAIPUR

Name of Work: Development of Grass Farm Nursery Khatipura, JDA, Jaipur

"G-Schedule"

(Based on PWD BSR 2013)

SI. No.	Description of work	Unit	Qty.	Rate	Amount (In Rs.)
	Part A: BSR Items				
1	Earth work in surface excavation not exceeding 30cm. in depth but exceeding 1.5 meter in width as well as10 Sqm on plan including disposal of excavated earth up to 50 Mtr. and lift up to 1.5 Mtr. disposed soil to be levelled and neatly dressed: All kinds of soil	sqm	1,750.000	25.00	43750.00
2	Providing and Laying of Interlocking M-30 grade Concrete Block Pavements having thickness 100 mm as per drawings and MoRD Specification Clause 1504with M-30 Grade 0.30 Mtr x 0.30 Mtr x 0.15 Mtr Edge Blocks. B) Category 'B': Dentated only two side like I,Z,T shape as per IRC:SP:63-2004	sqm	1,750.000	975.00	1706250.00
3	Earth work in excavation by mechanical means (Hydraulic Excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sum on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including taking out the excavated soil and depositing and refilling of jhiri with watering & ramming and disposal of surplus excavated soil as directed with in a lead of 50 meter. All kinds of soils	cum	554.400	124.00	68745.60
4	Providing and laying in position cement concrete including curing, compaction etc. complete in specified grade excluding the cost of centering and shuttering - All work up to plinth level.				
4.1	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size).	cum	1.440	2287.00	3293.28
4.2	M10 grade Nominal Mix 1: 3: 6 (1 cement : 3 coarse sand : 6 graded sto	cum	180.000	2665.00	479700.00
5	Providing and laying in position specified grade of cement concrete for RCC structural elements upto floor five level including curing, compaction, finishing with rendering in cement sand mortar 1:3 (1 cement: 3 coarse sand) and making good the joints and cost of plastizers (if required) excluding the cost of centering, shuttering and reinforcement for Walls (any thickness) including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc.M20 grade Nominal Mix / Design Mix	cum	2.250	4082.00	9184.50

6	Centering & shuttering with plywood or steel sheets including strutting, propping bracing both ways with steel props and removal of formwork for upto floor five level for: Suspended floors, roofs, landings, staircases, balconies, girders, cantilevers, bands, coping bed plates, anchor blocks, sills, chhajjas, lintel, beam, plinth beam etc.	sqm	20.160	236.00	4757.76
7	Providing and fabricating reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding (including cost of binding wire) all complete up to floor five level. Thermo-mechanically Treated bars (Conforming of relevent IS code)	Kg	180.000	69.00	12420.00
8	Brick work with F.P.S. bricks of class designation 75 in superstructure above plinth level upto floor V level in all shapes and sizes in : Cement mortar 1 : 6 (1 cement : 6 coarse sand)	cum	9.200	3277.00	30148.40
9	Random Rubble stone masonry for with hard stone in foundation and plinth in Cement Sand mortar above 30 CM thick wall in: Cement Mortar 1:6 (1-Cement : 6-Sand).	cum	9.600	1967.00	18883.20
10	Providing and fixing M.S. sheet 1mm thick single leaf door shutter in angle iron frame 35x35x5mm suitabilly diagonally braced with 25x3mm flat iron above and below lock rail of size 50x5mm beading extra including all fittings, as per direction of Engg. incharge but excluding cost of chowkhats: including two coats of anit-corrosive red oxide primer paint	sqm	1.000	2084.00	2084.00
11	Supplying and fixing fixed wire gauge of 14 mesh x 24 gauge to the metal frame of rolled section by metal beading 20x3mm with suitable screw at not exceeding 150mm distance.	sqm	1.215	428.00	520.02
12	Providing and fixing Square bars or other flat welded to window, ventilatiors etc.	Kg	10.000	62.00	620.00
13	P & F European type white glazed vitreous china 1st quality W.C pan (IS: 2556 Mark) with P or S trap including cutting and making good the wall and floor	Each	1.000	1295.00	1295.00
14	P & F water closet Seat Covers with brass hinges complete : Solid PVC (IS 2548 marked) grade-I White for EWC.	Each	1.000	322.00	322.00
15	P & F W.V.C. Urinal Partition Plate of approved standard make of size 630x315mm including making good the wall.	Each	3.000	823.00	2469.00
16	Labour charges for removing and refixing of urinals (all type & sizes) including all necessary fittings.	Each	3.000	247.00	741.00

17	P & F WVC wash basin (1st quality, I.S.: 2556 Mark) of approved make with C.I. brackets duly painted, 1 No. 15 mm C.P. Pillar cock (IS: 8934 Mark) & 32 mm C.P. brass waste coupling of approved make, 25 mm G.I. waste pipe complete including cutting & making good the wall.: Size 450 mm x 300 mm	Each	1.000	1481.00	1481.00
18	Providing and fixing 1st quality standard white, grey, ivory, fume red brown, light green, light blue and other light shades glazed tiles confirming to IS: 13753 & IS:15622 of size 200mm x 300mm in walls, floors, steps, pillars etc. laid on a bed of neat cement slurry finished with flush pointing in the white cement mixed with pigment to match the shade of the tile complete (excluding the cost of cement plaster on walls and pillar).	sqm	32.000	514.00	16448.0
19	Providing and fixing 1st quality MAT finished ceremic tile size 300x300mm confirming to IS: 13755 and IS: 15622 colour such as white, grey, ivory, fume red brown, light green, light blue and other light shades in floors, steps, pillars etc. laid on a bed of neat cement slurry finished with flush pointing in the white cement mixed with pigment to match the shade of the tile complete (including the cost of cement mortar bed 1:4).	sqm	15.000	563.00	8445.0
20	Plaster on new surface on walls in cement sand mortar 1:4 including racking of joints etc. complete fine finish: 20mm thick.	sqm	75.000	119.00	8925.0
21	Finishing wall with water proofing cement paint of approved brand and manufacture and or required shade to give an even shade including all scaffolding: New work (Two or more coats applied @ 3.84 kg/10 sqm).	sqm	75.000	37.00	2775.0
22	Random rubble dry stone Kharanja under floor.	cum	3.000	646.00	1938.0
23	Supply & fixing of M-20 grade precast cement concrete Kerb or Dand upto 60 cm length over 20 mm thick base of cement mortar 1:6 including jointing earth work, painting & jointing with cement mortar 1:4 of size (20 x 25) / 2 x 30 cm	R.Mtr.	4,000.000	350.00	1400000
24	Providing and fixing steel gate, grating, and grills made of angles, tees, square bars, flats, or black pipe with holdfast and fittings complete as per design and drawing including cutting welding and fabrication with priming coat of red oxide	Kg	150.000	74.00	11100.
	Part B: Non BSR Items				
25	Construction of jogging track on existing track using clay sand mix(design as approved by Rajasthan sports council) including grinding of clay and mixing by mechanical means prepration of bed, laying clay mix mechanically (Hydraulic system) and compacting using vibratory roller making surface levelledd and even including cost of water, hire charges of all T&P complete in all respect as direction by incharge.	cum	450.000	1160.00	522000

	84		Total		4479195.76
27	Providing and fixing mild steel dustbin consisting of size 600 x 600 & Height 800mm Dustbin is specially design for accomadating dry as well as wet kind of weste. The bucket of bin is made of 14 gauge steel sheet. Total wt. of dustin shall not be less than 45kg. design as per direction of Engineer in charge complete (Drawing Enclosed)	Each	10.000	5100.00	51000.00
26	Supply and fixing of ornamental & Floral Garden benches of cast iron sides with 12 No. of MS tubular pipes of size 65 x 22 mm medium section with provision of grouting at all the four base and bench ends suitably grinded and smooth surface finish and primer coated and deco painted with over all length 150 cm, 70 cm width and 80 cm height having over all weight 110 kg. including fixing of bench with J HOOK (16mm dia nad length minimum 45 cm.) in cement concert 1:2:4 (30cm x 30cm x 45cm) as per drawing and design (Drawing Enclosed)	Each	10.000	6990.00	69900.00

Executive Engineer (Garden)
JDA, Jaipur

1. I/We do hereby agree to do above work @	% above/below (In Figures) Schedule "G"
Amount.	
2. I/We do hereby agree to do above work @	above/below
(In Words) Schedule "G" Amount.	

Signature of Contractor with full Address and Mobile No.