

जयपुर विकास प्राधिकरण, जयपुर।

क्रमांक: जविप्रा/अ.अ.-3/2021/डी-125

दिनांक 05.10.2021

संशोधन सूचना


इस प्रकोष्ठ द्वारा जारी बिड सूचना संख्या-अधि.अभि.-3/04/2021-22 में वर्णित "PHQ रोड पर नवीनीकरण का कार्य" की BSR BOQ में Item Description में श्रुटिवंश गलत Item Description अंकित हो गया है। अतः BSR BOQ में Item Description को निम्नानुसार परिवर्तित किया जा रहा है एवं BSR BOQ की Qty, Unit & Rate पूर्व BSR BOQ की ही रहेगी। परिवर्तन निम्नानुसार है:-

Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1.00	Tack Coat Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per MoRD Specification Clause 503.	9000.00	Sqm	10.80	97200.00	INR Ninety Seven Thousand Two Hundred Only
2.00	Providing and laying bituminous concrete with 100-120 TPH batch type hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4 to 5.6 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRT & H Specifications Clause 509 complete in all respects for Grading-II (13 mm nominal size) Bitumen (VG-30)	828.00	P.MT	2934.00	2429352.00	INR Twenty Four Lakh Twenty Nine Thousand Three Hundred & Fifty Two Only
3.00	Marking Centre Line and stop lines etc. on road as per IRC pattern with thermoplastic paint of approved	553.00	Sqm	436.50	241384.50	INR Two Lakh Forty One Thousand Three

	quality and make with 8% glass beads laid on the road surface at temperature 160° C with a special applicator machine complete with labour material and traffic diversion arrangements.					Hundred & Eighty Four and Paise Fifty Only
4.00	Supplying of Cat's Eye made of aluminium alloy size 75x100x22 mm having 21 biconvex lenses embedded in circular disk of ABS plastic on each side.	1600.00	Each	180.00	288000.00	INR Two Lakh Eighty Eight Thousand Only
5.00	PAINTING Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : One or more coats on old work	1315.00	Sqm	18.00	23670.00	INR Twenty Three Thousand Six Hundred & Seventy Only
6.00	as per order no. JDA/TA to DE/07/D-1129 Dated 01.03.2007 Approved by Director (Engineering) P & F of cement concrete precast kerb or dand of M-20 grade upto 60 cm length over 20 mm thick base of cement mortar 1:6 including earth work, cutting of B/T road, cutting of WBM road etc. & jointing with cement mortar 1:4 grouted 125 mm in ground of shape as approved by Engineer-in-charge. The rates are inclusive of providing, laying and compacting base concrete 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate of 20 mm thick nominal size) 100 mm thick below dand/kerb complete in all respect. The size of kerb be 15 cm x 32.5 cm with round at top.	500.00	R.mtr	106.00	53000.00	INR Fifty Three Thousand Only
7.00	Interlocking Concrete Block Pavement with M-30 Grade 0.30 Mtr x 0.30 Mtr x 0.15 Mtr Edge Blocks (measurements shall be made inner to inner side of edge blocks) Providing and Laying of Interlocking M-30 grade Concrete Block Pavements having thickness 80 mm as per drawings and MoRD Specification Clause 1504 with M-30 Grade 0.30 Mtr x 0.30 Mtr x 0.15 Mtr Edge Blocks. Category 'B' : Dentated only two side like I,Z,T shape as per IRC:SP:63-2004	630.00	Sqm	693.00	436590.00	INR Four Lakh Thirty Six Thousand Five Hundred & Ninety Only

8.00	Providing and fixing Granite stone slab mirror polished and machine edge cut in walls, pillars, steps, Shelves, Sills Counters, Floors etc. laid on 12mm (Av.) thick base of cement mortar 1: 3 (1cement : 3 coarse sand) jointing with white cement mortar 1: 2 (1white cement : 2 marble dust) with pigment to match the shade of the marble slab including grinding, rubbing and polishing complete. Jhunjhunu/Jalore (Red/Chocolate Colour) Up to 1500 Cm2 Tiles	220.00	Sqm	1305.00	287100.00	INR Two Lakh Eighty Seven Thousand One Hundred Only
9.00	Refebrication work with existing steel work including cutting, welding & refebrication as per requirement with fixing at site complete as per direction of Engineer In charge	400.00	Kg	21.60	8640.00	INR Eight Thousand Six Hundred & Forty Only
10.00	Providing and fixing of Reinforced Ferro cement Drain cover designed for class "AA" loading duly marked on cover with adequate steel reinforcement having thickness 75 mm to 150 mm anti- corrosive bitumen painted M.S. plate Rim and on M.S. lifting hooks admixture like plasticizer bond improving compound shrinkage resistance compound abrasion resistant complete as per approved design etc. for drain Opeining Size 1201 to 1500 mm Standard Drain Cover Size 2100 mm x 500 mm x 150 mm	31.50	Sqm	2871.00	90436.50	INR Ninety Thousand Four Hundred & Thirty Six and Paise Fifty Only
11.00	Removing and Refixing of Pre cast Kerb stone obtained from site and fixing at as per direction of engineer-in-charge over 100 mm thick C.C. 1:4:8 and jointing of kerbs with cement mortar 1:4 including cost of loading unloading transporting and curing complete in all respect as per direction of Engineer-in-charge.	510.00	R.mtr	40.00	20400.00	INR Twenty Thousand Four Hundred Only

12.00	Removing & Refixing of precast concrete interlocking paving blocks recovered item from site 60 mm to 100 mm thick laid on average 50 mm thick bed of coarse sand joint be filled with fine sand laying procedure on compacted sub base as define etc. complete as per direction of Engineer-in-charge with all lead and lift.	600.00	Sqm	60.00	36000.00	INR Thirty Six Thousand Only
Total in Figures					4011773.00	INR Forty Lakh Eleven Thousand Seven Hundred & Seventy Three Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				


 अधिशाषी अभियन्ता-3,
 जविप्रा, जयपुर।