



JAIPUR DEVELOPMENT AUTHORITY, JAIPUR

www.jda.urban.rajasthan.gov.in

RE/D/EE (Elect-I) /2021/D- 435

Dated: 16/11/2021


CORRIGENDUM - 2

निवेदा संख्या 25/2021-22 की शर्तों में निम्नानुसार आंशिक संशोधन किया जाता है :-

Please read in BoQ item no. 37, 62-62.1, 63-63.1 as below:

1. SITC of 33/11 KV, 5 MVA star delta transformer on existing platform with one bucholdg, MOG, winding and oil temperature indicator complete in all respect as per latest specifications of Discoms including making necessary connection etc. (The Transformer will be tested by Discom).
2. SITC of BEE 3 star rated Aluminium wound Transformer conforming to IS: 2026 & Losses as per Discom's CTL (CTL Test certificate to be attached) of rating 11/0.433KV Delta-Star Connected, Vector Group Dyn 11, standard accessories like conservator, silica gel breather, radiator, fins, HT bushing & LT cable boxes, Off - LTC (+/- 5% in steps of 2.5%) winding temperature rise of 50/55 C, ISI marked drain valve, Dial type Temperature gauge, first fill of oil, Epoxy based paint, including carrying of pre-commission Testing & Charging of Transformer. (See table - 08 for CTL Losses). 100 KVA
Qty. :1 Rate: 149600.00
3. Supply & Erection of lattice structure of height 11 mtr in alignment, including excavation of pit and Providing and laying of cement concrete in ratio 1:3:6 using 43 grade cement, river sand and 12 mm to 20 graded blast crusher broken in pit/ found cement plaster upto 0.50mtr. from top to bottom in 1:3:6 ratio and paint of tower of approved make two coat of red oxide paint and one coat of aluminium paint before installation and one coat of paint after irrection work completed as per technical specifications & drawing of DISCOM.
Complete Rate Group-1
Qty. :14 Rate: 24400.00

निवेदा की अन्य सभी शर्तें यथावत रहेगी।


16/11/2021
Executive Engineer (Elect-I)
JDA, Jaipur