


JAIPUR DEVELOPMENT AUTHORITY, JAIPUR



Bid Document

For

Name of work:- Rate contract for two years for providing laying jointing of sewer lines with manholes under PHE-II jurisdiction JDA Jaipur.

Cost: Rs. 189.94 Lakh

**Executive Engineer (PHE-II)
Jaipur Development Authority
Jaipur**

जयपुर विकास प्राधिकरण, जयपुर

क्रमांक: जविप्रा/अधि.अभि.(पीएचई-।।)/2023/डी-399

दिनांक : 21.09.2023

बिड़ आमंत्रण सूचना

निविदा संख्या-अधि.अभि.(पीएचई-।।)/08/2023-24

जयपुर विकास प्राधिकरण द्वारा "अधिशायी अभियन्ता पीएचई-।।, जविप्रा के क्षेत्राधिकार में दो वर्षीय दर संविदा के अन्तर्गत सीवर लाईन बिछाने एवं जोड़ने मय आपूर्ति का कार्य" जिसकी अनुमानित लागत रुपये 189.94 लाख के लिए ऑनलाईन निविदा दिनांक 03.10.2023 सांय 6:00 बजे तक आमंत्रित की जाती है। निविदा बोली का ऑनलाईन आवेदन व भुगतान जविप्रा पोर्टल पर करने की अन्तिम तिथि दिनांक 03.10.2023 को सांय 6:00 बजे तक है। निविदा बोली के दस्तावेजों का विस्तृत विवरण www.sppp.raj.nic.in व www.eproc.rajasthan.gov.in एवं www.jda.urban.rajasthan.gov.in पर देखा जा सकता है।

1. (UBN No.)

निविदा में भाग लेने वालों को निम्न शर्तों की पूर्ति करनी होगी :-

1. निविदा दाता जयपुर विकास प्राधिकरण की वेबसाइट www.jda.urban.rajasthan.gov.in पर पंजीकृत हो एवं निविदा में भाग लेने के लिए बोलीदाता को आवेदन करने के लिए दस्तावेज शुल्क, अमानता राशि, आर.आई.एस.एल. प्रोसेसिंग शुल्क ऑनलाईन जमा करनी होगी।
2. ऑनलाईन निविदा प्रस्तुत करने के लिए निविदा दाताओं का राजस्थान सरकार के ई-प्राक्यूमेंट पोर्टल www.eproc.rajasthan.gov.in पर पंजीकृत हो।

अधिशायी अभियन्ता (पीएचई-।।)
जविप्रा, जयपुर

प्रतिलिपि:-

1. जन सम्पर्क अधिकारी, जविप्रा को तकनीकी सहायक (निदेशक अभियान्त्रिकी-तृतीय) के मार्फत समाचार पत्र में प्रकाशन हेतु।
Job No. JDA/EE PHE II/A & F/2023-2024/Sep/426 dt. 21.09.2023 Rs. 1,97,53,157/-

अधिशायी अभियन्ता (पीएचई-।।)
जविप्रा, जयपुर

JAIPUR DEVELOPMENT AUTHORITY, JAIPUR

Room No. 307, Citizen Care center Building, Ram Kishore Vyas Bhavan, Indira Circle, Jawaharlal Nehru Marg,
Jaipur – 302 004

Telephone: +91-141-2569696 email: eephe2@gmail.com

No.:-JDA/EE(PHE-II)/2023/D-399

Dated:- 21.09.2023

BID NOTICE INVITING

NIB No. : EE (PHE-II)/ 08/2023-24

Online Bids are invited upto 6.00 PM of 03.10.2023 for “Rate contract for two years for providing laying jointing of sewer lines with manholes under PHE-II jurisdiction JDA Jaipur” Estimated cost **Rs. 189.94 Lakh.** The Last date of for applying bid and making online payment on JDA portal is up-to 6.00 PM of 03.10.2023. Details may be seen in the Bidding Document at our office or the State Public Procurement Portal website www.sppp.rajasthan.gov.in, www.eproc.rajasthan.gov.in and www.jda.urban.rajasthan.gov.in

1. (UBN No.)

To participate in the bid, bidder has to be:

1. Registered on JDA website www.jda.urban.rajasthan.gov.in For participating in the Bid, the Bidder has to apply for the Bid and pay the Bidding Document Fee, RISL Processing Fee and Bid Security Deposit, online only.
2. Registered on e-Procurement Portal of Government of Rajasthan www.eproc.rajasthan.gov.in for online e-Bid submission.

Executive Engineer (PHE-II)
JDA, Jaipur

Copy to :-

1. PRO Cell, JDA, Jaipur through TA to DE (III) for publication in News paper.

Job No. JDA/EE PHE II/A & F/2023-2024/Sep/426 dt. 21.09.2023 Rs. 1,97,53,157/-

Executive Engineer (PHE-II)
JDA, Jaipur

Detail NIB for uploading on SPP Portal, e-Procurement, JDA Protal & as part of NIB Document

JAIPUR DEVELOPMENT AUTHORITY, JAIPURRoom No. 307, Citizen Care center Building, Ram Kishore Vyas Bhavan, Indira Circle, Jawaharlall Nehru Marg,
Jaipur – 302 004Telephone: +91-141-2569696 email: eephe2@gmail.com

No.:-JDA/EE(PHE-II)/2023/D-399

Dated:- 21.09.2023

BID NOTICE INVITING**NIB No. : EE.(PHE-II)/08/2023-24**

Name & Address of the Procuring Entity	➤ Name: Executive Engineer (PHE-II), Jaipur Development Authority ➤ Address: Room No. 307, Citizen Care center Building, Ram Kishore Vyas Bhavan, Indira Circle, Jawaharlal Nehru Marg, Jaipur-302 004 (Rajasthan) ➤ Email: eephe2@gmail.com
Subject Matter of Procurement	➤ Rate contract for two years for providing laying jointing of sewer lines with manholes under PHE-II jurisdiction JDA Jaipur. ➤ Job No. JDA/EE PHE II/A & F/2023-2024/Sep/426 dt. 21.09.2023 Rs. 1,97,53,157/-
Bid Procedure	➤ Single-stage tender (Single envelope) open competitive eBid procedure at http://eproc.rajasthan.gov.in
Bid Evaluation Criteria (Selection Method)	➤ L 1(eg. Least Cost Based Selection (LCBS) -L-1
Websites for downloading Bidding Document, Corrigendum's, Addendums, etc.	➤ Websites: www.sppp.rajasthan.gov.in, www.eproc.rajasthan.gov.in, www.jaipurjda.org
Website for online Bid application participation and payment	➤ Website: www.jda.urban.rajasthan.gov.in ➤ For participating in the Bid, the Bidder has to apply for this Bid and pay the Bidding Document Fee, RISL Processing Fee and Bid Security Deposit, online only. ○ Bidding document fee: Rs. 1000/- Rupees (One Thousand only) ○ RISL Processing Fee: Rs. 1500/- Rupees (One Thousand Five Hundred only) - Requisite Bid Security Deposit
Estimated Procurement Cost	➤ INR Rs. 189.94 Lakh (Rupees One Crore Eighty Nine Lakh Ninety Four Thousand Only)
Bid Security Deposit	➤ Amount (INR): 2% (Rs. 3,79,880/-) (For A & AA class contractor registered in other department) of Estimated Procurement Cost, 0.5% of S.S.I. of Rajasthan, 0.5% (Rs. 94,970/-) (For Contractor registered B and Above Class in JDA) for Bidder registered as contractor in JDA, 1% for Sick

	Industries, other than S.S.I., whose cases are pending with Board of Industrial & Financial Reconstruction. ➤ In case of Department's of the State Government and undertakings] Corporations, Autonomous bodies, Registered Societies, Cooperative Societies which are owned or controlled or managed by the State Government and Government undertakings of the Central Government shall submit a bid securing declaration in lieu of bid security.
Date/Time/place of Pre-Bid	➤ N/A
Applying Bid and making online payment on JDA portal (www.jda.urban.rajasthan.gov.in)	➤ Bid Start Date: 22.09.2023 at 9.30 AM ➤ Bid End Date: 03.10.2023 at 06.00 PM ➤ In case EMD in form BG Original Bank Guarantee is to be submitted in Room No. CCC-TF-307 of Citizen Care Centre JDA, Jaipur by 04.10.2023 10.00 AM to 06.10.2023 up to 11.00 AM
Bid submission on e-Procurement Portal of GOR (WWW. Eproc.rajasthan.gov.in)	➤ Bid Start Date: 22.09.2023 at 09.30 AM ➤ Bid End Date: 03.10.2023 at 06.00 PM
**Date/ Time/ Place of Technical Bid Opening	➤ NA
Date/ Time/ Place of Financial Bid Opening	➤ 06.10.2023 at 2:00 PM ➤ Room No. 307, Citizen Care Centre, Third Floor, Ram Kishore Vyas Bhavan, Indira Circle, Jawaharlal Nehru Marg, Jaipur-302 004 (Rajasthan)
Bid Validity	➤ 120 days from the date of opening of bid.
Time Period	➤ 24 Months
* Jaipur Development Authority has decided to receive Earnest Money Deposit (EMD) (Bid Security), Tender Fee and RISL processing fee online through JDA Portal. The bid security options available in tender for participants are a Mentioned Below:	

A. Payment Options:

Option-1: Bank Guarantee (BG) against EMD/ Bid Security

Bidder may opt Bank Guarantee (BG) against EMD (Bid Security), for which bidder requires to prepare BG before applying in the tender. The details of BG requires to be fed on JDA portal before paying balance amount (Tender Fee + RISL Processing Fee). This amount will be paid through Payment Gateway only, option to make balance payment through EFT (RTGS/NEFT) will not be available. If bidder does not opt for BG against EMD, options of making complete payment through Payment Gateway or through EFT (NEFT / RTGS) will be available.

Option-2: Electronic Fund Transfer (EFT: NEFT/RTGS)

If the bidder selects payment mode as EFT (NEFT/RTGS), "Paying Slip for EFT (NEFT/RTGS)" will be generated by the system for the complete amount. The payment can be made from any Bank any Branch using this Paying Slip through NEFT/RTGS (Claim against payment made through EFT in any other JDA bank account will not be acceptable and bidder stands disqualified from participation in the bid applied for). After successful transaction through NEFT/RTGS, as per the standard procedures it may take 4 to 24 hours in process of confirmation of EFT through Auto-Process depending on the time of EFT done. Therefore, option to make payment through EFT (NEFT/RTGS) will be available till 48 hours prior to closing date of bid participation.

Option-3: Payment Gateway (Aggregator)

The facility to make payment through Debit Card, Credit Card, Net banking etc., will be available. User can use this facility from anywhere any time till the closing date & time of bid participation.

B. Bid Participation Receipt

After confirming payment, the bidder will get Bid Participation Receipt on the basis of which user will get the payment details along with other details for bidding on e-Procurement portal of GOR.

- In case of BG as the remaining payment will be done through Payment Gateway, on successful transaction the "Bid Participation Receipt" will be generated on real time basis.
- In case complete payment is done through Payment Gateway, on successful transaction the "Bid Participation Receipt" will be generated on real time basis.
- In case complete payment is done through EFT (NEFT/RTGS), on confirmation of payment from ICICI Bank (Auto Process) "Bid Participation Receipt" will be available on Login of Bidder on JDA portal.

Note:

1. Bidder (authorized signatory) shall submit their offer on-line in Electronic formats both for technical and financial proposal.
2. In case, any of the bidders fails to pay the Tender Fee, BSD, and RISL Processing Fee, online (subject to confirmation), its Bid shall not be accepted.
3. To participate in online bidding process, Bidders must procure a Digital Signature Certificate (Type III) as per Information Technology Act-2000 using which they can digitally sign their electronic bids. Bidders can procure the same from any CCA approved certifying agency, i.e. TCS, Safe crypt, N code etc. Bidders who already have a valid Digital Signature Certificate (DSC) need not procure a new DSC. Also, bidders must register on <http://eproc.rajasthan.gov.in> (bidders already registered on <http://eproc.rajasthan.gov.in> before 30-09-2011 must register again).
4. JDA will not be responsible for delay in online submission due to any reason. For this, bidders are requested to upload the complete bid well advance in time so as to avoid 11th hour issues like slow speed; choking of web site due to heavy load or any other unforeseen problems.
5. Bidders are also advised to refer "Bidders Manual Kit" available at eProc website for further details about the e-Tendering process.
6. Training for the bidders on the usage of e-Tendering System (e-Procurement) is also being arranged by DoIT&C, GoR on a regular basis. Bidders interested for training may contact e-Procurement Cell, DoIT&C for booking the training slot.
Contact No: 0141-4022688 (Help desk 10 am to 6 pm on all working days) e-mail: eproc@rajasthan.gov.in Address : e-Procurement Cell, JDA, Yojana Bhawan, Tilak Marg, C-Scheme, Jaipur
7. The procuring entity reserves the complete right to cancel the bid process and reject any or all of the Bids.
8. No contractual obligation whatsoever shall arise from the bidding document/ bidding process unless and until a formal contract is signed and executed between the procuring entity and the successful bidder.
9. Procurement entity disclaims any factual/ or other errors in the bidding document (the onus is purely on the individual bidders to verify such information) and the information provided therein are intended only to help the bidders to prepare a logical bid-proposal.
10. The provisions of RTPPA Act 2012 and Rules thereto shall be applicable for this procurement. Furthermore, in case of any inconsistency in any of the provisions of this bidding document with the RTPPA Act 2012 and Rules thereto, the later shall prevail.

Executive Engineer (PHE-II)
JDA, Jaipur

Process for Participation & Depositing Payment Online

JAIPUR DEVELOPMENT AUTHORITY, has decided to receive Bidding document fee, RISL Processing Fee and Bid Security Deposit (BSD) through online mode only for which the bidder has to get registered himself on JDA portal

www.jda.urban.rajasthan.gov.in.

To participate in the bid, bidder has to be:

1. Registered on JDA website www.jda.urban.rajasthan.gov.in (by depositing Rs. 500.00 online, the validity of which remains 3 (three) years).

For participating in the Bid, the Bidder has to apply for this Bid and pay the Bid Document Fee, RISL Processing Fee and Bid Security Deposit, online only.

2. Registered on e-Procurement Portal of Government of Rajasthan www.eproc.rajasthan.gov.in for online e-Bid submission.

Methods for depositing on line amount

Option-1: Bank Guarantee (BG) against EMD / Bid Security

Bidder may opt Bank Guarantee (BG) against EMD (Bid Security), for which bidder requires to prepare BG before applying in the tender. The details of BG requires to be fed on JDA portal before paying balance amount (Tender Fee + RISL Processing Fee). This amount will be paid through Payment Gateway only, option to make balance payment through EFT (RTGS/NEFT) will not be available.

If bidder does not opt for BG against EMD, options of making complete payment through Payment Gateway or through EFT (NEFT / RTGS) will be available.

Option-2: Electronic Fund Transfer (EFT: NEFT/RTGS)

If the bidder selects payment mode as EFT (NEFT/RTGS), “Paying Slip for EFT (NEFT/RTGS)” will be generated by the system for the complete amount. The payment can be made from any Bank any Branch using this Paying Slip through NEFT/RTGS (Claim against payment made through EFT in any other JDA bank account will not be acceptable and bidder stands disqualified from participation in the bid applied for). After successful transaction through NEFT/RTGS, as per the standard procedures it may take 4 to 24 hours in process of confirmation of EFT through Auto-Process depending on the time of EFT done. Therefore, option to make payment through EFT (NEFT/RTGS) will be available till 48 hours prior to closing date of bid participation.

Option-3: Payment Gateway (Aggregator)

The facility to make payment through Debit Card, Credit Card, Net banking etc., will be available. User can use this facility from anywhere any time till the closing date & time of bid participation.

C. Bid Participation Receipt

After confirming payment, the bidder will get Bid Participation Receipt on the basis of which user will get the payment details along with other details for bidding on e-Procurement portal of GOR.

- In case of BG as the remaining payment will be done through Payment Gateway, on successful transaction the “Bid Participation Receipt” will be generated on real time basis.
- In case complete payment is done through Payment Gateway, on successful transaction the “Bid Participation Receipt” will be generated on real time basis.

In case complete payment is done through EFT (NEFT/RTGS), on confirmation of payment from ICICI Bank (Auto Process) “Bid Participation Receipt” will be available on Login of Bidder on JDA portal.

While participation in the bid, a receipt will be generated through the system showing the submission details as per Bid Participation Receipt (Sample Enclosed). The bidder is required to fill the instrument numbers for various heads on e-Procurement portal www.eproc.rajasthan.gov.in as mentioned in the receipt.

Jaipur Development Authority, Jaipur. Bid Participation Receipt			
			Date & Time:-
Bid Detail			
Bid ID:		Procurement Entity:-	
Bid Title:			
Bid Value:		Bid Opening Place:	
Bidder Detail			
Name of Entity:		Mobile No.:	
Registration Type:		Instrument Amount:	
Payment Mode:		Payment Channel:	
Instrument No.:		Instrument Date:	
Dates Detail			
Sr. No.	Event Name		Event Date
1	Bid Publishing Date		
2	Bid Opening Date		
Specific Instrument for eProc Rajasthan			
Instrument Type			
Instrument Number	Head Name	Amount	Date
	Tender Fee		
	RISL Processing Fee Bid Security Deposit		
Issuer Detail: Jaipur Development Authority		Challan Number:	

More details about Registration Process, Terms and Conditions and FAQ along with contact detail is available on JDA website www.jda.urban.rajasthan.gov.in.

Jaipur Development Authority, Jaipur

Office Order

No. : JDA/IT(1074501)/E-Services/2015-16/D-399

Dated: 4-10-2016

Subject: Payment mechanism for participating in tender.

Jaipur Development Authority has decided to receive Earnest Money Deposit (EMD) (Bid Security), Tender Fee and RISL processing fee online through JDA Portal. The bid security options available in tender for participants are as mentioned below:

A. Payment Options:

Option-1: Bank Guarantee (BG) against EMD / Bid Security

Bidder may opt Bank Guarantee (BG) against EMD (Bid Security), for which bidder requires to prepare BG before applying in the tender. The details of BG requires to be fed on JDA portal before paying balance amount (Tender Fee + RISL Processing Fee). This amount will be paid through **Payment Gateway only**, option to make balance payment through EFT (RTGS/NEFT) will not be available.

If bidder does not opt for BG against EMD, options of making complete payment through Payment Gateway or through EFT (NEFT / RTGS) will be available.

Option-2: Electronic Fund Transfer (EFT: NEFT/RTGS)

If the bidder selects payment mode as EFT (NEFT/RTGS), "Paying Slip for EFT (NEFT/RTGS)" will be generated by the system for the complete amount. The payment can be made from **any Bank any Branch** using this Paying Slip through NEFT/RTGS (Claim against payment made through EFT in any other JDA bank account will not be acceptable and bidder stands disqualified from participation in the bid applied for). After successful transaction through NEFT/RTGS, as per the standard procedures it may take 4 to 24 hours in process of confirmation of EFT through Auto-Process depending on the time of EFT done. Therefore, option to make payment through EFT (NEFT/RTGS) will be available till 2 days prior to closing date of bid participation.

Option-3: Payment Gateway (Aggregator)

The facility to make payment through Debit Card, Credit Card, Net banking etc., will be available. User can use this facility from **anywhere any time** till the closing date & time of bid participation.

B. Bid Participation Receipt

After confirming payment, the bidder will get Bid Participation Receipt on the basis of which user will get the payment details along with other details for bidding on e-Procurement portal of GOR.

- In case of BG as the remaining payment will be done through Payment Gateway, on successful transaction the "Bid Participation Receipt" will be generated on real time basis.

Page 1 of 2

- In case complete payment is done through Payment Gateway, on successful transaction the “**Bid Participation Receipt**” will be generated on real time basis.
- In case complete payment is done through EFT (NEFT/RTGS), on confirmation of payment from ICICI Bank (Auto Process) “**Bid Participation Receipt**” will be available on Login of Bidder on JDA portal.

This payment mechanism will come into force w.e.f 15/10/2016. Thereafter, old payment mechanism related to NEFT/ RTGS in which the bidder makes direct payment without “**Paying Slip for EFT (NEFT/RTGS)**” in JDA’s bank account will be discontinued.

All procuring entities are hereby directed to clearly mention this procedure in NIB document.


(Pawan Arora)
Secretary

Copy for information and further necessary action to:

1. P.S. to JDC, JDA, Jaipur.
2. P.S. to Secretary, Secretary, JDA, Jaipur.
3. Director (Law / Finance / Town Planning / Engineering-I / Engineering-II), JDA, Jaipur.
4. All Additional Chief Engineer _____, JDA, Jaipur
5. DC (Administration)/DC(Store)/DC (Vehicle), JDA, Jaipur
6. System Analyst, JDA, Jaipur
7. Analyst-cum-Programmer, JDA to ensure integration of software w.e.f 01/10/2016.
8. All Xen _____, JDA, Jaipur.
9. Officer-in-charge, SPPP Portal, Jaipur.
10. OSD (Public Relation) / PRO, JDA, Jaipur.


(Brijesh Kishore Sharma)
OSD (RM)

FORM OF BANK GUARANTEE

Form of (Bank Guarantee) -En cashable at branch of the bank in Jaipur City.

To

Secretary,

Jaipur Development Authority,

Jaipur

Sub:-.....

Bank Guarantee No. _____ dated _____ for [amount of Security in figures] [in words] on behalf of _____ [Name of the Bidder] against the Security Deposit for the work of **“Rate contract for two years for providing laying jointing of sewer lines with manholes under PHE-II jurisdiction JDA Jaipur”**.

WHEREAS, _____ [name of Bidder with address] (hereinafter called **“the Bidder”**) has submitted his Bid dated for the work of **“Rate contract for two years for providing laying jointing of sewer lines with manholes under PHE-II jurisdiction JDA Jaipur”** (hereinafter called **“the Bid”**).

KNOW ALL PEOPLE by these presents that we _____ (Name of Bank) of having our registered office at _____ [name of country] having our registered office at _____ (hereinafter called **“the Bank”**) are bound unto Secretary, Jaipur Development Authority. (Hereinafter called **“the Employer”**) in the sum of Rupees _____ **[Amount of Security in figures]** _____ (in words) only for which payment will and truly to be made to the said Employer, the Bank binds itself, its successors, and assigns by these presents. That on demand of JDA, this Bank Guarantee is encashable at following branch in Jaipur City.

1. Name of Bank:
2. Name of the branch with branch code:
3. Address:
4. E-Mail Id:
5. Telephone No.
6. Fax No.:

SEALED with the Common Seal of the said Bank this _____ day of _____ of 20_____.

THE CONDITIONS of this obligation are:

- (1) if the Bidder withdraws his Bid during the period of Bid validity specified in the Form of Bid;
- (2) if the Bidder refuses to accept the correction of errors in his bid;
- (3) If the Bidder, having been notified of the acceptance of his Bid by the Employer during the period of Bid validity;
 - (a) fails or refuses to execute the Form of Agreement in accordance with the Instructions to Bidders, or
 - (b) fails or refuses to furnish the Performance Security, in accordance with the Instructions to Bidders;

We undertake to pay to the Employer up to the above amount upon receipt of his first written demand, without the Employer having to substantiate his demand, provided that in his demand the Employer will note that the amount claimed by him is due to him owing to the occurrence of one or more of the above conditions, specifying the occurred condition or conditions.

This Guarantee will remain in force up to and including the date 30 days after the date of expiration of the Bid Validity, as stated in the Instructions to Bidders, or any such extension thereto as may be agreed by the Bidder, notice of which extension(s) to the Bank is hereby waived. Any demand in respect of this Guarantee should reach the Bank not later than the above date.

The amount covered under the above Bank Guarantee shall be automatically be credited in the accounts of JDA in ICICI Bank, JDA Campus, Jaipur through **IFSC code No ICIC0006754. Bank Account No. 675401700518** on the date of expiry or its validity, unless the agencies get it re-validated well before its expiry date or produce NOC from JDA in written for its release.

Date _____ Signature of the Bank _____

Witness _____ Seal _____
[Signature, Name and Address]

[Note: To be furnished on appropriate non-judicial stamps.]

Section A-1

Instructions to Bidders

JAIPUR DEVELOPMENT AUTHORITY, JAIPUR

SCHEDULE AND SPECIFICATIONS

Name of work :- Rate contract for two years for providing laying jointing of sewer lines with manholes under PHE-II jurisdiction JDA Jaipur.

1. NIB No. :- E.E.(PHE-II)/08/2022-23
2. Approximate cost :- Rs. 189.94 Lakh
3. Cost of the tender documents :- Rs 1,000/-
4. Earnest Money :- Rs. @ 0.5 % Rs. 94,970/-
(For Contractors Enlisted B & Above Class in JDA, Jaipur)
:- Rs. @ 2 % Rs. 3,79,880/-
(For Contractors Enlisted in other Govt. Deptt.–“A” & “AA” Category)
5. Bid Submission Start date & Time :- 22.09.2023 (09:30 AM)
6. Bid Submission End date & Time :- 03.10.2023 (upto 6:00 P.M.)
7. Bid Opening date & Time :- 06.10.2022 at 2:00 P.M.
8. Completion period of work :- 24 Months

SCHEDULE 'A' : INFORMATION USEFUL FOR THE CONTRACTORS :

The tenderer should see the site and fully understand the condition of the site before tendering and include all lead, lifts etc. **Percentage above/Below on the rates as given in the 'G'-Schedule.** The work shall be carried out in accordance with the Rajasthan PWD, PHED and JDA detailed specification and to the entire satisfaction of the Engineer-In charge of the work.

The bid will be opened only of those bidders deposit proper bid security, processing fee, tender fee, GST registration, clearance certificate and copy of registration of contractor in required category are found to be in order. The Bid security, tender fee will be accepted through online payment only.

SCHEDULE 'B' : LIST OF THE DRAWING TO BE SUPPLIED BY THE DEPARTMENT:

The drawings may also be seen in the office of undersigned.

SCHEDULE 'C' : LIST OF THE DRAWING TO BE SUPPLIED BY THE CONTRACTOR:

List of the drawing to be supplied by the contractor NIL. But the contractor shall have to arrange at his own cost drawings required for the work after depositing necessary cost within JDA.

SCHEDULE 'D' : TEST OF THE MATERIALS :

The test of the material and workmanship shall be conducted by the JDA staff as necessary, The result of such tests should confirm to the standard laid down in the Indian standards and or the standards laid down in the detailed specification of the Public Works Deptt.,. Proper quality control is required to be maintained by the contractor. Qualified personnel as required under the contractor enlistments rules duly approved by the Deptt. shall have to be engaged at site by the contractor. The deptt. reserves the right to engage such staff and recover the expenses from the contractor on such account in case of his failure to do so.

SCHEDULE 'E' : SAMPLES OF THE MATERIALS :

The samples of the material to be used by the contractor shall be deposited **15 days** in advance with the Engineer In charge and be got approved by him before use.

SCHEDULE 'F' : TIME OF COMPLETION :

The work should start within Ten days of issue of work order and complete within **24** months.

SCHEDULE 'H' : SPECIAL CONDITION.

- 1. In case of single bid system Annexure "B" enclosed by the bidder regarding qualification of RTPP Act 2012 & Rule 2013 along with bid document, should be signed by the participating bidder before uploading the tender document otherwise the bid of the bidder will be rejected.**
- 2. After dated 31.12.2022 contractor cannot participate in bid without Review Registration**

Annexure A : Compliance with the code of Integrity and No Conflict of Interest

Annexure B : Declaration by the Bidder regarding Qualifications

Annexure C : Grievance Redressal during Procurement Process

Annexure D : Additional Conditions of Contract

Annexure E : DLP period for various type of works. Office order D-29 dated 11.03.2016

Annexure F : Payment mechanism for participating in tender: Office order D-399 dated 04.10.2016.

Annexure G : GST Circular for participating in tender: Office order D-172 dated 12.07.2017.

Annexure H : Finance (G&T) department, notification dated 22.10.2021

Annexure I : JDA Order D-75 dated 26.08.2021

Annexure J : Finance (G&T) department, notification dated 12.01.2022

Annexure K : JDA Office Order No. JDA/EE & (TA to Dir. Engg.-I)/2022/D-194 dated 06.09.2022

SIGNATURE OF CONTRACTOR

**Executive Engineer (PHE-II)
Jaipur Development Authority,
Jaipur**

with full address & Mobile No. :

TENDER FOR WORKS

I/We hereby tender for the execution for the Jaipur Development Authority, Jaipur of the work specified in the underwritten memorandum within the time specified in such memorandum at the rates, (in figure)% (as well as in words) Percent below/above the amount, entered in the schedule G in all respects in accordance with the specifications, designs, drawings and instructions in writing referred to in Rule I in all respects in accordance conditions with such conditions so far as applicable. I/We have visited the site of work and am/are fully aware of all the difficulties and conditions likely to affect carrying out the work, I/We have fully acquainted myself/ourselves about the conditions in regard to accessibility of site and quarries/kilns nature and the extent of ground, working conditions including stacking, of materials, installation of tools & plant, conditions effecting accommodation and movement of labour etc. required for the satisfactory execution of contract.

Memorandum

- | | | | |
|-----|---------------------------------------|---|--|
| (a) | General description of work..- | : | |
| (b) | Estimated cost | : | Rs. 189.94 Lakh |
| (c) | Earnest money | : | Rs. 3,79,880/- @ 2 %
(For A & AA Class enlisted contractors outside of JDA) |
| | | : | Rs. 94,970/- @ 0.5 %
(For B & Above Class enlisted in JDA contractors) |

- (d) **Security Deposit :**

(i) "The security deposit @ 10% of the gross amount of the running bill shall be deducted from each running bill and shall be refunded as per rules on completion of the contract as per terms and conditions. However, the amount of security deposit deducted from running bills shall not be converted into any mode of securities like bank guarantee. FDR etc. The earned money deposited shall however be adjusted while deducting security deposit from first running bill of the contractor. There will be no maximum limit of security deposit.

However, a contractor may elect to deposit of full amount of 10% security deposit in the shape of bank guarantee or any acceptable form of security before or at the time of executing agreement. In that case earnest money may be refunded only after deposition of full 10% as above. However, in case during execution cost of works exceeds as shown at the time of depositing 10% as above, balance security deposit shall be deducted from the Running Account Bills."

(ii) Bank Guarantee shall in all cases be payable at the headquarter of the Division or the nearest District Headquarters.

- (e) Time allowed for the completion of work (to be reckoned from the 10th day after the date of written order to commence the work) in **24 months**. Should this tender be accepted in whole or in Part, I/We hereby agree to abide by and fulfill all the terms and provisions of the conditions of contract annexed here to and of the Notice Inviting Tender, or in default thereof, to forfeit and pay to the Governor of Rajasthan or his successors in office, the sum of money mentioned in the said conditions.

Validity of rates 120 days.

A sum of Rs. is forwarded herewith in the form of Cash, Bank Draft, Bankers Cheque as Earnest Money. This amount of earnest money shall absolutely be forfeited to the Governor of Rajasthan or his successor in office without prejudice to any other right or remedies of Governor of Rajasthan or his successor in his office, should I/We fail to commence the work specified in the above memorandum.

Signature of Witness
Witness's address & Occupation

Signature of Contractor
Address of Contractor

Date:

The above tender is hereby accepted by me on behalf of the Governor of Rajasthan

Date:

Executive Engineer (PHE-II)

Section A-2

General Conditions of Contract

(Appendix XI of PWF & AR. Govt. of Rajasthan effective
up to date shall be applicable)

Section A-3

Special Conditions of Contract

SPECIAL CONDITIONS OF THE CONTRACT**1 PROVISION FOR NOMINAL REINFORCEMENT IN PRE-CAST RINGS**

The Contractor shall provide steel reinforcement as per design requirement in each Pre-Cast M-40 Grade Circular Rings, along with nominal **reinforcement @ 0.12%** of gross cross sectional area in both the direction i.e. vertical bar & circular rings) subject to a minimum of nominal reinforcement as per Code of "*Practice of Plain and Reinforced Concrete*" IS:456 2000. **No extra payment shall be made to him/firm on this part. The Contractor should therefore take provisions accordingly.**

SETTING OUT

2. The contractor(s) shall set out the whole of the work in conjunction with an officer to be deputed by the Engineer-in-charge and during the progress of the work to amend on the requisition of the Engineer-in-charge any errors which may arise therein and provide all the necessary Labour materials and equipments for so doing. The contractor has to provide all tools, plant, machinery, Labour and materials which may be necessary and required for the work. All materials and workmanship shall conform to the relevant specifications mentioned in the tender documents.
3. The contractor shall carryout the detailed topographic survey (level survey) with in the site and prepare the pre-commencement maps for approval of the Engineer-in-charge. Based on the approved pre-commencement maps showing spot levels of road crossing, the contractor will prepare the necessary working drawings and L-sections for the purpose of execution of work.

Public Awareness / Information Display

4. The contractor shall, at his own cost, arrange to provide, erect and maintain necessary display boards/ flags/banners etc. at selection points of project site giving such information as considered necessary for public awareness/ information/ safety as directed by the Engineer-in-charge.
5. Contractor shall provide sufficient number of boards at site of work indicating "**JDA AT WORK**" at his own cost as required by Engineer-in-charge.

Site office for Engineer-in-charge and other supervisory staff

6. The contractor shall arrange to provide office at his own cost with two tables, five chairs, two steel almirah, display board, etc., fully furnished office accommodation within 15 days from the date of commencement of work as per requirements/ directions of the Engineer-in-charge including maintenance of the same.

Field Laboratory

7. Within 15 (fifteen days) from the date of commencement of work, the contractor shall arrange to provide at his own cost a fully furnished and adequately equipped field laboratory.
8. The calibration of the laboratory equipment and instrument shall at the initial stages be certified by agencies approved by the Engineer-in-charge. Laboratory equipment shall be properly maintained and calibrated throughout the period of the contract by the
9. Contractor at his own expense. The contractor shall notify the Engineer-in-charge sufficiently in advance prior to conducting any tests for materials at work. The Engineer-in-charge will also inspect the laboratory and the contractor shall provide adequate facilities to the Engineer-in-charge for his independent verification of the accuracy and adequacy of the facilities.

Requirement of Land

10. Land for establishment of site office, field laboratory etc. shall be arranged by the contractor at his own cost.

Transport of material is contractor's responsibility.

11. It shall be mandatory on the part of the contractor to arrange Crane of suitable size for the transportation, loading, unloading, and fixing in position of the Pre-cast manhole elements. No manual labour for such purpose shall be engaged.
12. The tested material will be transported to site by the contractor safely. If any material or pipe/pre-cast elements got damaged during transportation, loading, unloading, stacking and lowering in the trench the same will be rejected and no payment shall be made.
13. The surplus earth and damaged materials will be immediately removed from the site of work and dumped as per instruction of Engineer-in-charge.
14. The material collected at site and paid provisionally shall remain under the watch and ward of the contractor till it is consumed fully on the work.
15. Any material not conforming to the specifications collected at site shall have to be removed by the contractor within a period of 3 days of the instructions, issued by the Engineer-In-charge in writing. failing which, such material shall be removed by the Engineer-In-charge at risk and the contractor after expiry of 3 days period.

Inspection of work/ Materials.

16. **The testing of work /samples shall be carried out by Engineer-in-charge/authorized representative or by Third party inspection as selected and directed by the Engineer-in-charge. The test shall be carried out as per relevant I.S. Specification at manufacture's site before transportation to site. Inspection cost/testing charges if any, shall be born by the contractor only. Inspection shall be carried out for various items for HDPE DWC pipes/RCC pipes, PVC (SWR) pipes, Cast iron ring and frame, manhole cover Ferro-cement footsteps and Pre-cast manhole elements/components etc.**

The cost of samples including transportation's as well as of the testing shall be borne by the contractor. The third party agency for HDPE DWC pipe shall be any one of the following:-

1. M/s CEIL
2. M/s RITES
3. M/s SGS

Or "by any other" as approved by Engineer-In-Charge

Sewer laying work and construction of manholes.

17. The JDA Site Engineer shall provide the reduced level value of Bench Marks and invert levels in reference to the Bench Marks while starting the work. The contractor/ Firm or company's technical staff will transfer levels in the trench to lay the sewer line at required gradient with standard level instruments and , boning rods, side rails. The Contractor/Firm or company will be fully responsible for any error while transferring levels from Bench Marks to the trench. While doing so, if any, line is laid wrongly and/or is not as per desired gradient it shall be the responsibility of contractor to get the line re-laid at his own cost
18. The contractor shall provide at the site all material he shall be required to use for timbering/stuttering shoring excavation of trenches and which he shall bring to the site, prior to start of excavation for approval of the Engineer-in-charge.
19. Pre-cast manhole chambers shall be constructed/assembled simultaneously with the laying of sewers as per drawing and detailed specification of **JDA BSR.**
20. Concreting work should be done in the presence of an Engineer-in-charge not below the rank of Site Engineer of the JDA after checking of reinforcement by the Sector Engineer. After taking layout, the contractor shall submit daily Schedule of work to the Engineer-in-charge 15 days in advance.
21. Only design mix concrete of grade M-40 shall be used for the precast manhole elements.

22. The contractor shall keep the trenches open between two consecutive manholes while laying the sewer line. Pipes shall be lowered in the trenches and cured minimum for three days, trench shall be refilled with excavated earth as per specification after the inspection of Sector / Site Engineer.
23. No extra payment will be made to the contractor on account of clearance of soakage well/septic falling in the alignment of the sewer line. The sewer line shall be tested at contractor's cost as per I.S. code no. 783-1985 and departmental specifications for water tightness, straightness and gradient by the Engineer In charge. If any leakage is found during testing the same will be replaced by the contractor at his own cost.
24. Two percent amount of each running bill shall be with held on account of testing of sewer system, which will be released only after successful testing. The contractor will be fully responsible for structural safety stability and water tightness of the sewer line and associated work.

Materials

25. Cement and steel shall not be supplied by the department.
26. Steel, when arranged by the contractor shall produce a test certificate for the whole lot as per the IS Code provisions from an authorized laboratory approved by the Engineer-in-charge.
27. Water for construction and testing purpose shall have to be arranged by the contractor at his own cost. In case it is supplied by the JDA, charges @ 1% of total value of item of construction work shall be taken and recovered from each running bill.

Design and Drawings.

28. JDA shall not be responsible for any error, in accuracy or permission of any kind in JDA's requirements as originally included in the contract. Any data or information received by the Contractor, from JDA or otherwise, shall not relieve the Contractor from his responsibility for the design and execution and structural stability of the per-cast elements.
29. The drawings of the pre-cast eccentric conical piece and circular rings is based on the departmental designs. Contractor may study the design, drawings and specifications carefully and if felt necessary, may increase the sectional thickness, reinforcement or the grade of concrete suitably. No extra payment shall be made to the contractor over the rates quoted by the contractor for any modifications / changes proposed by him. The contractor shall be fully responsible for the structural safety of the precast manhole elements/components.

As Built Drawings.

30. The submission of the as-built drawings of the sewer work is the precondition for the final payment. The final drawings shall be submitted in one reproducible set and 3 copies on linen bound in an album of an approved size. The contractor shall submit all the completion drawings **including L-Section and point file** and approved design calculations on CD ROM / DVD in two copies with proper directory structure. The scale of drawing and the size of drawing shall be as per the direction of the Engineer in Charge.

Safety aspects associated with the work.

31. **Safety And Accident Prevention Officer:** Due precautions shall be taken by the Contractor, at his own cost, to ensure the safety and protection against accidents of all staff and Labour engaged on the works, local residents in the vicinity of the works, and the public traveling through the works. The contractor shall deploy at least one officer from his staff, qualified to promote and maintain safe working practices. This/these officer(s) shall has/have authority to issue instructions and shall take protective measures to prevent accidents, including but not limited to the establishment of safe working practices and the training of staff and labor in their implementation. The contractor shall furnish to the department the name(s) of such officer(s) before the start of the work.
32. The contractor/firm or company while executing the work will adopt all safety measures at his cost to safeguard from any loss of life and damage of public and private property. If any loss and damage is occurred, they will pay the full compensation from their own pocket to the concern. All the consequence (legal and or financial) will be borne by the contractor only and JDA will not be responsible in any way.

33. The contractor shall not work before sunrise and after the sunset.
34. The contractor/firm or company will take utmost care to safeguard the water mains, Electric and Telephone cable existing surface drains water connections etc., while executing the work. Any damages/rectification shall be borne by the contractor only .
35. The contractor/firm/company is bound to get the workmen insured against accident from the Insurance Company at his own cost.
36. The contractor will pay compensation to the house owner or to the owner of any adjoining property or any other works for the damaged sustained on account of this work while in progress or complete from his own pocket.
37. Electric and water connections, if needed, shall be arranged by the contractor himself at his own cost.
38. Contractor shall be the sole custodian of the men and material at work and will be fully responsible for any loss of life or otherwise occurred during the execution of the works

39. Defects liability period

The defect liability period shall be of 3 years, from the date of the completion. The Contractor shall be responsible for satisfactory performance of the work under all design and operation conditions for the duration of the defects liability period, except for damages due to unprecedented natural calamities.

40. Refund of Performance Guarantee & Security Deposit

The Security Deposit (SD) and Performance Guaranty (PG) shall be refunded after successfully completion of defect liability period of 3 years. The 20 % amount of SD shall be released after completion of 1st year of DLP, other 20 % amount of SD shall be released after completion of 2nd year of DLP and remaining 60 % amount of SD shall be released after completion of 3rd year of DLP. (As per JDA Office order no. JDA/EE(TA to Dir.-Engg-I)/2016/D-29 dated 11.03.2016)

- 41. As per office order no. JDA/DD (E&B)/2018/D-352 dated 29.08.2018, Clause of agreement no. 45 for Price Escalation variation is not applicable.**

COMMISSIONS AND CORRECTIONS

42. If there is any typographical error or otherwise in the 'G' Schedule. The nomenclature and the rates as given in the relevant **JDA PHE BSR (Sewerage & Water Supply) 2014-2015 & JDA BSR-2016** rates on which schedule 'G' is based, shall prevail.

The above conditions may be read very carefully and adhered strictly.

Signature of Contractor

**Executive Engineer (PHE-II)
JDA, Jaipur**

Section A-4

Specifications and Scope of Work

SPECIFICATION AND SCOPE OF WORK

1. **The site is located at various locations under Jurisdiction of Executive Engineer (PHE-II), JDA Jaipur.**
 - a) Setting out of works and carrying out confirmatory survey.
 - b) Submission of working design and drawings and approval of same by the department.
 - c) Providing, laying and jointing of 200 mm diameter HDPE DWC, 200 mm Dia RCC NP-4 & 250 mm dia RCC NP-3 pipe line.
 - d) Construction of new manholes with RCC Pre Cast Conical piece and RCC Pre Cast Rings as per enclosed drawings and specifications.
 - e) Utility shifting.
 - f) Restoration of Roads.
 - g) Inspection of material at works.
 - h) Removal of defects in laying and jointing of all sewers, fittings and manholes after testing and during defect notice periods.
 - i) The drawings enclosed in **Section-A6**, appended herewith contains a plan of the area, The Schedule 'G' in volume II contains item wise classification of underground strata likely to be excavated but the same is not guaranteed and excavation work may have to be carried out in different strata other than given in schedule 'G'.
 - j) Submission of as built drawings.
 - k) Any other associated work as required by Engineer-in-charge.
 - l) Prior to vacating the site, the contractor shall be responsible for and bear any costs of reinstating the site to a condition at least equal to that in which it was handed over to the contractor.
- The contractor is advised to visit site of work before quoting his rate and frame his own opinion about the live conditions prevailing at site.**

2. DESCRIPTION OF WORK.

- a) The complete work will be consisting of the following main items as specified in detailed schedule and drawings as per the tender document enclosed herewith.
- b) Excavation of trenches, refilling and removal or surplus earth for laying pipes and construction of appurtenances like manhole and vent shaft along with requisite safety measures.
- c) Providing, laying and Jointing **200 mm dia HDPE DWC, 200 mm dia RCC NP-4 & 250 mm dia RCC NP-3 pipes at** required gradient and testing of joints and associated works.
- d) Providing and laying suitable bedding of cement concrete for pipes.
- e) Construction of required size RCC Pre Cast Manholes along with providing and fixing Ferro cement Manhole covers, C.I. frames and Ferro cement footsteps of required size, duty and weight as per drawing.
- f) Making connection to existing Sewers by dismantling wall and concrete channel and its related repairs.
- g) The drawings enclosed in section A-5 appended herewith contains a plan of the area, The Schedule -G in volume II contains item wise classification of underground strata likely to be excavated but the same is not guaranteed and excavation work may have to be carried out in different strata other than given in schedule-G.
- h) The contractor is advised to visit site of work before quoting his rate and frame his own opinion about the live conditions prevailing at site.
- i) Any other associated work as required by Engineer-in-charge.

2.1 DRAWING TO BE SUPPLIED BY CONTRACTOR

The following drawings are required to be supplied by the tenderer when required by the Engineer-in-charge and work should commensurate only after obtaining his approval in writing.

- a) Drawing of measuring boxes for cement, sand and other construction material supplied at site.
- b) Drawing of Ferro-cement manhole covers with cast iron ring, frame and Ferro-cement steps supplied at site.
- c) **AS-BUILT DRAWINGS:-**The submission of the as-built drawings for the equipment is the precondition for the final payment. The final drawings shall be submitted in one reproducible set and 3 copies on linen bound in an album of an approved size. The contractor shall submit all the **completion drawings, including L- section man hole to man hole with point file and approved design calculations on CD ROM / DVD in two copies with proper directory structure.** The scale of drawing and the size of drawing shall be as per the direction of the Engineer in Charge. Any other drawings related to works included in the contract.

2.2 DRAWINGS TO BE SUPPLIED BY THE DEPARTMENT.

The drawings of the various manhole elements (Ferro-cement manhole cover, Ferro cement footsteps, Cast iron rim and frame), drawings showing the trench width for various invert depth of the corresponding diameters and the map/plan of the area showing the proposed lateral sewer network is enclosed in the section A-5 of the tender document shall be supplied by the department.

2.3 WORKING DRAWING:

The working drawings showing plan and positions of proposed sewers are available for inspection at the office of the undersigned. The interested may inspect these drawings during office Hrs. on any working day.

2.4 GENERAL DESIGN OBLIGATIONS

- a) The Contractor shall be deemed to have scrutinized, prior to submission of bid, design criteria, calculations, and drawing as per the JDA requirements.
- b) JDA shall not be responsible for any error, in accuracy or permission of any kind in JDA's requirements as originally included in the contract. Any data or information received by the Contractor, from JDA or otherwise, shall not relieve the Contractor from his responsibility for the design and execution of the works.

2.5 SUBMISSION PROCEDURE FOR DETAILED DESIGN AND EXECUTION DRAWINGS:

- a). The contractor shall carry out the preparatory works such as to prepare the plans, L-Section, designs, working drawings etc.
- b). The drawings shall be sufficient in details and the scale has to be chosen accordingly in coordination with the Engineer in charge.
- c). If required, the detailed design and the execution drawings shall be submitted only after verification by an institute or agency approved by the Engineer In charge or any authorized representative of the JDA.

3. SAMPLES OF MATERIAL

- 3.1** The Contractor shall submit samples of the following items, to the Engineer In charge for carrying out tests as specified under Schedule 'D' in specified quantities as mentioned against each item before the commencement of work or within 15 days of issue of order, whichever accrues earlier and shall obtain his approval before using any such material at site free of cost by the contractor.

a) Rubble stone / Brick (First Class)	10 Nos.
b) Fine Aggregate (Bajari)	0.05 Cum.
c) Coarse Aggregate:	
Size 20mm and below	0.05 Cum
d) Steel (for each size of bar)	0.05 Kg.
e) Spun Yarn	0.05 Kg.
f) Cement	One bag.
g) Bitumen Paint.	0.05 kg.

The following samples shall be submitted from each lot of supply as per I.S.S. for approval of Engineer In charge as to the quality of material. These samples shall be returned to the Contractor after completion of work.

a) HDPE/DWC Pipes ISI marked.	5 Nos
b) RCC NP-4 & RCC NP-3 Pipes ISI marked	5 Nos
c) Ferro cement steps for manholes	1 No
d) Ferro cement manhole cover	1 No
e) Pre-cast RCC manhole element	1 No.

- 3.3** Any other sample of material that may be required by the Engineer In charge from time to time.

- 3.4** All the above samples are to be delivered in suitable packing at the office of the Executive-Engineer-In – charge or as desired by the engineer-in-charge

4. TESTS OF MATERIALS

The Engineer In charge or his authorized representative will carry out tests as and when considered necessary for the quantity and quality of work done and for the material used at the work. The contractor, unless otherwise specifically mention to do so, shall provide all facilities and arrangements to undertake those tests.

- 4.1** The contractor shall provide all necessary facilities to undertake tests for a lot of material supplied at site. All the testing charges for the test being conducted on construction material such as HDPE/DWC pipes, RCC NP-4 & RCC NP-3 pipes, concrete, manhole cover, cement, fine aggregate, coarse aggregate etc at other/departmental Testing laboratories shall be borne by the contractor

- 4.2** The testing of all the building material shall be conducted as per relevant Indian Standard specification. If relevant Indian standard specifications are not available for a particular item, the testing for quality of material shall be done in accordance with detailed specification of PWD (B.S.R.) Rajasthan, however it is not possible for the contractor to take suitable arrangements for testing of sample the same shall be taken to the laboratory authorized by the Executive Engineer-in-charge. The contractor shall get the quality of material obtained from each source approved from the Engineer In charge. In case the source of supply of building

material is changed at subsequent date sample as required above shall be got approved before using the material.

- 4.3** The samples submitted by the contractor required under schedule –G, Volume -II shall invariably be supplemented with the manufacturer's test certificate for approval of the Executive Engineer In charge. The Executive Engineer, in charge may ask for further testing of material before, approval and subsequent use at site. The contractor in such case shall supply required quantity of samples as desired by Executive Engineer, in charge. The samples as obtained shall be sent to authorized laboratory for testing. In case the material is not found to be as per specification the whole lot of supply shall be rejected.

The relevant standards for complying testing and specification for each material are as given below:

1. HDPE/DWC pipe : IS 16098 part-2 (As amended upto date)
2. RCC pipes: IS 458 As amended upto date)
3. Ferro cement circular manhole cover and frames as per (Departmental specifications and drawing).
4. Ferro cement foot steps for manholes.
5. Precast manhole elements (Departmental specifications and drawing).

5. LIST OF MATERIAL TO BE SUPPLIED BY THE DEPARTMENT

Nil.

6. DETAILED SPECIFICATIONS

The detailed specifications of the work to be executed shall be as per the provision of detailed specification JDA PHE BSR 2014-2015 (Sewerage & Water Supply), **JDA BSR-2016** and the relevant Indian standard specifications unless otherwise mentioned above in the specification for work explained under scope of work. Wherever a reference to the I.S. code mentioned herein appears, it shall be taken as reference to the latest edition of the standard. The complete scope and detailed specification of work is as detailed herein after, item wise given in Schedule 'G' and drawings given in, volume-II and section A-5 of bid document respectively.

6.1 TRANSFER OF LEVELS AND ESTABLISHMENT OF GRADIENTS:

- a) The contractor should furnish his work program, construction methodology within 15 days after the letter of Notice to proceed for work and prior to start of the construction activities at site.
- b) To carry out the leveling survey of whole area or part of the area as a confirmatory survey as per Engineer-in-charges instructions and confirm the ground levels, chain age, road network, etc. with the data available in design reports and got it approved from the Engineer-in-charge prior to commencement of the work.
- c) The transfer of level at ground from the specific bench mark (to be given with in 100 meter from the starting point of line) shall be done by contractor. The grade line shall be done with the help of sight rail and boning rods. The necessary equipment and manpower required shall be arranged by contractor for transfer of levels.

6.2 EXCAVATION AND REFILLING WORKS

- a) The excavation and refilling work shall be done in accordance with the detailed specification PWD (B.S.R.) Rajasthan and as per drawing appended in section A-5.
- b) The provision of IS 3764/1966 safety code for excavation work and is 4091-1967 safety code for blasting and related drilling operation shall be strictly met with at each site of work. The work shall be stopped in case these requirements are not met with.
- c) Excavation work for different size of sewers, manholes, as per working drawings in different soils / described item wise in schedule 'G' shall be carried out in the manner specified here in drawing No.1.
- d) Before excavating the trench the alignment of sewer line shall be approved by the Engineer.
- e) Before carrying out the excavation work the trial pits shall be taken along the proposed sewer line alignment by the contractor after mutual agreement and approval of the Engineer in advance of the excavations for the purpose of satisfying himself as to the location of underground obstructions or conditions. The contractor shall proceed with caution, in any excavation and shall use every means to determine the exact location of underground structures, pipelines, conduits etc, and prior to excavation in the immediate vicinity thereof. The contractor shall be solely responsible for the cost of protections or repair or replacement of any structure, pipeline, conduit etc, above or below ground which may be broken or otherwise damaged by his operations.
- f) The trench shall be shored and timbered wherever necessary and specified. The blasting and dewatering work shall be carried out in the manner specified and all material and T & P shall be arranged by the contractor at his own cost. All hard and soft patches shall be treated in the manner specified after obtaining approval from Engineer-In-charge. Unless the description of items for excavation specified so, separate measurement shall not be taken for these time.
- g) The lighting, barricading, guarding of the trenches and the provision of watchman shall be done by the contractor at his cost.
- h) The barricading shall in no case be removed until the trench is excavated, the pipes are laid and Engineer-in-charge gives permission to proceed with the backfilling
- i) Contractor shall not be paid any additional compensation for excess excavation over what is specified as well as for any remedial measures that are specified.

- j) The excess excavated material shall be carried away from the site of works as specified, failing which in view of public safety and traffic convenience, Engineer-in-charge may carry out the work by any other agency at Contractors risk and cost.

6.3 UNDER BED AND BEDDING WORK BELOW PIPES.

- a) The type of bedding as per specification of G schedule, working drawing along with under bed, where ever, required shall be provided in stages and manners specified in drawings and as per directions of engineer-in-charge. The complete material placement in specified dimensions and specified levels, connection etc. is included in scope of work.
- b) The bedding shall preferably be provided continuously between consecutive manholes. In case, it is not possible to do so, the vertical joints in bedding material shall be provided at outer edge of socket. No horizontal joints shall be permitted in concrete cradle.

6.4 SUPPLYING, LAYING, JOINTING AND TESTING OF PIPES:

- a) Full round HDPE DWC (double wall corrugated) pipes of SNB grade as per IS 16098 specification for "HDPE DWC pipe and fitting". HDPE DWC pipes with spigot and socket ends of size and class as per working drawings, specifications given herein after and in standard length specified therein shall be supplied at site of work. No extra measurements will be taken for increase in number of joints on account of shorter lengths of pipe use and also for cutting of pipes wherever required as per site conditions. Any balance pipe lengths from a cut or rejected pipe lengths including their cost of transportation to and from the site will not be measured separately.
- b) The RCC S&S NP-4 & NP-3 pipes ISI Marked shall be supplied conforming to IS:458:1988 (Amended up to date) with anticorrosive bitumenastic paint of approved brand two or more coats (make Shalimar or equivalent) with ISI marked rubber ring/gasket lubricant etc.
- c) The laying and jointing of pipes shall be done in accordance with I.S. 4127-1967 "Code of practice of laying glazed stone ware pipes".
- d) The laying and jointing of RCC S&S NP-4 & NP-3 pipes shall be done in accordance with IS: 783: 1995 (Amended up to date) with hydraulic testing of sewer line.
- e) All pipes supplied shall be free from cracks, chipped ends and irregular angular space between pipes and socket /spigot end and should have smooth interior finish. All pipes shall be subjected to sound test by a suitable wooden hammer and ensured against invisible cracks. Any defective pipe, even after lowering into the trench shall be rejected and shall be immediately removed from site. The storage of pipes at site shall be in accordance with the provisions of ISS 4032-1977.
- f) The pipe shall be lifted towards alignment of sewer line covered and laid in the trenches, in the manner specified with equipments like chain-pulley etc. all arrange by the contractor. Any pipe damaged during above operation shall be removed and replaced by the contractor at his cost. Any material falling into the trench while lowering or otherwise shall be removed and trenches shall be kept clear all the time.
- g) The pipes fittings and other construction material shall be placed along the alignment in advance with utmost care during transit so that they are not damaged. Any damage due to these reasons shall be Contractor's liability.
- h) Laying of the pipe prior to install the pipe bedding in the pipe trench, the Trench Bottom Level (TBL) shall be checked to confirm the slope and relative depth with respect to design level and got it approved from the Engineer. At first stage bedding shall be done up to pipe bottom level and same shall be checked before laying the pipe. At second stage the remaining bedding shall be done with proper careful compaction and finally the pipe top level shall be checked to confirm the proper slope.
- i) All the sewer lines are to be laid perfectly true both in alignment and to gradient specified. In case of spigot and socket pipe, the socket end of the pipe shall face upstream.
- j) The sewer lines shall be laid such that the making on pipes appears at the top of the pipes.
- k) Properly fitted temporary wooden stoppers shall be provided to close the ends of all incomplete sewer line. The stoppers are only to be removed when pipes are being laid and jointed. Opening of sewer at end of day's work shall be capped and sealed.
- l) Sewer pipe laying and jointing shall be started and completed only section wise as per the instruction of the Engineer-in-charge. The sections shall be chosen manholes to manhole. However in unavoidable circumstances the section of sewer line shall be changed as per site condition and as directed by Engineer. The work of sewer line laying, manhole construction and vent shaft shall be done simultaneously so that all the necessary testing can be done efficiently. The construction of the works should progress from downstream end (i.e. the discharge point) and proceed towards upstream. Also, as the work to facilitate the house sewer connection shall be done simultaneously, it will help in the commissioning of the works. As far as possible the testing of pipeline shall be done from manhole to manhole.
- m) The bedding for sewer lines shall be provided as specified in the drawings and as per direction of the Engineer.
- n) After 24 Hrs. of PCC bedding and laying of pipe line the trench shall be filled up to top of pipe with moist soil. The trench can be filled up to the top of the pipe level with moist soil to ensure curing of concrete and then after testing of sewer line, trench should be filled. In the duration before filling the trench, soil should be kept moist to ensure adequate curing.
- o) All the testing of sewer lines and other appurtenances, at both factory and site shall be carried out in presence of the Engineer or his representative.

- p) Special arrangements such as cranes, tripods with chain pulley block for lowering the pipes and fittings shall be made by contractor at his own cost. In no case pipes and fittings shall be dropped.
- q) The payment for the sewer lines and manholes shall be made only after satisfactory testing of the works, as directed by the Engineer.
- r) The reinstatement of road/footpath shall be done as specified and as per the requirements of the local authorities, on completion of all the works.

6.5 CONSTRUCTION OF MANHOLE CHAMBER AND TESTING FOR WATER TIGHTNESS.

- a) The manholes shall be circular and constructed as RCC insitu for varying invert depths as per design and specification. The manholes shall generally conform to relevant I.S. and departmental specifications. The location of manhole shall be as per the drawing or layout given by the Engineer-in-charge or as directed by the Engineer-in-charge. The Manhole dimensions and other details shall be as per the enclosed drawing. The location of manholes shall be as per drawing or layout given by the Engineer-in-charge.
- b) The inspection and testing of manhole chambers frames and covers shall be done at factory in presence of Engineer or his representative or shall be got done through third party inspection. The load test for covers shall be done in accordance with Table 1 of IS 12592 (Part -I).
- c) The entire height of the manhole shall be tested for water tightness as per CPHEEO Manual or relevant IS code. The required water for testing and any other requirements shall be arranged by the Contractor at his own cost. .
- d) The testing shall be preferably be done between manhole to manhole lengths. In case of steep slopping sewers, the test pressure at lower end of pipe, length tested should not exceed the allowable static pressure, the pipe length should be subdivided, and plug at end shall be effectively fixed. The pipe length under test shall be charged gradually. The pipe length under test should remain filled with water at least 24 hrs. Before testing.
- e) Any defect noticed during the testing shall be immediately repaired removed and replaced. The testing should again be repeated if it satisfies above requirements. The test water should be left in pipe during bedding and back filling operations.

6.6 MAKING CONNECTION WITH EXISTING SEWER.

- a) The connections in the existing sewer where required as per working drawings shall be made by cutting precast manhole walls preferably by using core cutting machine or other suitable means as specified by Engineer-in-charge. .

6.7 WORK TO FACILITATE HOUSE SEWER CONNECTION:

The work involves the laying of 110mm dia PVC (SWR) Grade 'B' pipes from the street manholes to property boundaries / roadside chambers to the as per drawings, site layout and as directed by the Engineer-in-charge to facilitate house sewer connections. UPVC pipes are to be plugged with end cap and concrete post near the property boundaries as shown in the Drawing and / or as directed by the Engineer.

No work shall be carried out inside the property boundaries.

6.8 OTHER SERVICES

Contractor shall take the necessary precautions to avoid the damage to other services such as water supply lines, telephone cables, electrical cables, storm water drains etc. In case of any damages to any of the services, Contractor shall be responsible for restoring the facilities in bare minimum time at his own cost.

6.9 PRECAST REINFORCED CONCRETE

PRECAST REINFORCED CONCRETE

6.9.1 GENERAL REQUIREMENTS

- a) Concrete used for pre-casting the units should be well proportioned, mixed, placed and thoroughly compacted by vibrations or tamping to give dense concrete free voids and honey combing.
- b) Pre-cast articles shall have a dense surface finish showing no coarse aggregate and shall have no cracks or crevices likely to assist in disintegration of concrete or rusting of steel or other defects that would interfere with the proper placing of the units. All angles of the precast units with the exception of the angles resulting from the splayed or chamfered faces shall be true right angles. The arises shall be clean and sharp except those specified or shown to be rounded. The wearing surface shall be true to the lines. On being fractured, the interior of the units should present a clean homogeneous appearance.

6.9.2 CURING

- a) After having been cast in the mould or form the concrete shall be adequately protected during set-ting in the first stages of hardening from shocks and from harmful effects of frost, sunshine, drying winds and cold. The concrete shall be cured at least for 14 days from the date of casting.
- b) The precast articles shall be matured for 28 days before erection or being built in so that the concrete shall have sufficient strength to prevent damage to units when first handled.

6.9.3 MARKING

Precast units shall be clearly marked to indicate the top of member and its location and orientation in the structure.

6.9.4 MIX DESIGN PROPORTIONING

- a) Mix proportions shall be designed to ensure that the workability of fresh concrete is suitable for conditions of handling and placing, so that after compaction it surrounds all reinforcements and completely fills the formwork. When concrete is hardened, it shall have the stipulated strength, durability and impermeability.
- b) Determination of the proportions by weight of cement, aggregates and water shall be based on design of the mix.
- c) As a trial the manufacturer of concrete may prepare a preliminary mix according to provisions of SP: 23-1982. Reference may also be made to ACI 211.1-77 for guidance.
- d) Mix design shall be tried and the mix proportions checked on the basis of tests conducted at a recognized laboratory approved by the Engineer-in-charge.
- e) All concrete proportions for various grades of concrete shall be designed separately and the mix proportions established keeping in view the workability for various structural elements, methods of placing and compacting.

6.9.5 STANDARD DEVIATION

Standard deviation calculations of test results based on tests conducted on the same mix design for a particular grade designation shall be done in accordance with clause 9.2.4 of IS 456:2000

6.9.6 ACCEPTANCE CRITERIA

The acceptance criteria for compressive strength and flexural strength designation shall be done in accordance with the relevant clauses of the IS codes.

6.9.7 DESTRUCTIVE TESTS

- a) Load Test: Contractor shall make necessary arrangement for load test of precast units at manufacturer's site. The load test shall be carried out by Engineer-in-Charge or by Third Party after approval of Engineer-in-Charge.
- b) Core test : Core test, if ordered by the Engineer-in-charge, shall be done in accordance with IS 516. Samples for such test shall be taken from locations to be identified by the Engineer-in-charge and such samples shall be collected in compliance with IS 1199.

6.9.8 NON DESTRUCTIVE TESTS

In case of doubtful structural strength non-destructive testing of the pre-cast manhole elements shall be done as per the instructions of Engineer-in-charge. Such tests may be any one or a combination of the following:-

1. REBOUND HAMMER TEST
2. WINDSOR PENETRATION PROBE TEST
3. PULSE VELOCITY (SONIC OR ULTRASONIC) TEST

Interpretation of Rebound Hammer, Windsor Probe and Pulse-velocity test results shall rest with the Engineer-in-charge.

6.9.9 SPECIFICATION FOR RCC ECCENTRIC CONICAL PIECE IN M40 GRADE.

The work involves construction of Pre-cast RCC M-40 grade circular manhole chamber of designated diameter 1000/1200/1500 for various invert depths including required excavation of earth in all types of soils such as murrum, sand, sandy silt, black cotton soil, hard soil, kankar etc. disposing of surplus excavated material within a lead of 50 meter. The work includes laying of 150 mm thick plain cement concrete 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 20 mm nominal size) 1600/1800/2100 mm diameter bedding in foundation, providing and laying of plain cement concrete 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate) in channel & circular starter base wall up to 50 mm above outer dia. of sewer pipe and P&F in position of 125 mm thick 150/225 mm high Pre-Cast M-40 grade cement concrete ring at bottom and consecutive standard size 300 mm high rings. The work includes P&F pre-cast reinforced cement concrete eccentric conical piece of M40 grade, 125 mm thick having 560 mm and 1000/1200/1500 mm internal diameter at top & bottom respectively, fitted with Ferro-cement cover of 33 kg cast iron double seal ring & frame (heavy-duty) etc to withstand for class AA loading including supply and fixing of Ferro-cement foot steps and sealing of all joints with cement mortar 1:1 complete job as per detailed specifications, drawings and directions of Engineer-In charge.

The height of the M-40 grade cement concrete circular rings of manhole can be increased only after the approval of Engineer-in-Charge subject to a maximum height of 1.20 m for which no extra payment shall be made to the contractor.

6.9.8.1 TOP ECCENTRIC CONICAL PIECE.

- a) Providing and fixing of Pre-cast RCC M-40 grade concrete eccentric conical piece for manhole manufactured using Weight Batching Plant.
- b) Only Design Mix Concrete of Grade M-40 shall be used.
- c) Shape:- Eccentric frustum of cone of designated diameter and thickness as per the enclosed drawings and specifications
- d) Testing: Apart from the usual strength test on of the concrete mix non-destructive test for strength of the concrete is to be carried out on sample piece of pre-cast manhole elements as per the instruction of engineer-in-charge.

6.9.8.2 CIRCULAR RINGS.

- a) Providing and fixing of Pre-cast M-40 grade cement concrete circular rings for manhole chambers manufactured by using Weight Batching Plant.
- b) Only Design Mix Concrete of Grade M-40 shall be used.
- c) Shape:- Circular in shape with end keys at top and bottom of designated diameter, height and thickness as per the enclosed drawings and specifications. The height of rings can be increased in the multiples of 30cms after inspection and approval of Engineer-in-Charge.
- d) Testing: Apart from the usual strength test on of the concrete mix non-destructive test for strength of the concrete is to be carried out on sample piece of pre-cast manhole elements lot as per the instruction of engineer-in –charge

6.9.8.3 The contractor shall be responsible for the quality of the works during the executions of works with good Engineering practices. He shall, therefore, have his own independent and adequate setup for ensuring the same.

7.0 CONTRACTOR'S STAFF AND EQUIPMENT

- a) The contractor shall employ for the execution of the work only such persons as are skilled and experience in all activities required for the completion of the work, from reconnaissance surveys to detailed design, manufacturing, and execution and testing to commissioning.
- b) The contractor shall provide either one graduate or one diploma Engineer to supervise the construction of the work and to act as the contractor's Representative. The Engineer shall be B.E. Civil Eng. with minimum 1-year experience or a diploma in Civil Eng. with minimum 3 years experience in the field of sewer line work. The contractor shall also provide sufficient skilled, semi-skilled and un-skilled labor as are necessary to ensure completion of the various sections of the work in the time required the contractor shall not deploy/remove any supervisory staff or Labour from the site without approval of the Engineer in charge.
- c) The Engineer in charge shall be at liberty to object and direct the contractor to remove from the work any person who in the opinion, of the engineer in charge misconduct himself or is incompetent or negligent in the proper performance of his duties such person shall not be again employed without permission of the engineer in charge.
- d) The contractor shall at all times during progress of the work take all requisite precautions and use his best endeavors to prevent any notorious or unlawful behavior by or amongst the workers and other persons employed on the works and for the preservation of peace and protection of the inhabitants and the security of property in the neighborhood of the work.
- e) The contractor shall, if required by the Engineer in charge deliver to him a return in detail in such form and at such intervals as the Engineer in charge may prescribe, showing the supervisors and Labour employed by the contractor on the site The contractor shall make his own suitable arrangements for lodging and boarding of his, Labour supervisors and engineers

8.0 PROGRESS OF WORK

All components of works shall ensure a logical sequence of supply, installation, testing, and commissioning. If any supply of a material is made, not in conformity to the logical sequencing of the work component, no payments will be entitled against such supplies and installations.

Executive Engineer (PHE-II)
JDA, Jaipur

Section A-5

Annexure

Compliance with the code of Integrity and No Conflict of Interest

Any person participating in a procurement process shall –

- (a) Not offer any bribe, reward or gift or any material benefit either directly or indirectly in exchange for an unfair advantage in procurement process or to otherwise influence the procurement process;
- (b) Not misrepresent or omit the misleads or attempts to mislead so as to obtain a financial or other benefit or avoid an obligation;
- (c) Not indulge in any collusion, Bid rigging or anti-competitive behavior to impair the transparency, fairness and progress of the procurement process;
- (d) Not misuse any information shared between the procuring Entity and the Bidders with an intent to gain unfair advantage in the procurement process;
- (e) Not indulge in any coercion including impairing or harming or threatening to do the same, directly or indirectly, to any party or to its property to influence the procurement process;
- (f) Not obstruct any investigation or audit of a procurement process;
- (g) Disclose conflict of interest, if any; and
- (h) Disclose any previous transgressions with any Entity in India or any other country during the last three years or any debarment by any other procuring entity.

Conflict of Interest :-

The Bidder participating in a bidding process must not have a Conflict of interest.

A conflict of interest is considered to be a situation in which a party has interests that could improperly influence that party's performance of official duties or responsibilities, contractual obligations, or compliance with applicable laws and regulations.

i. A Bidder may be considered to be in Conflict of Interest with one or more parties in a bidding process if, including but not limited to:

- a. Have controlling partners/shareholders in common ; or
- b. Receive or have received any direct or indirect subsidy from any of them; or
- c. Have the same legal representative for purposes of the Bid; or
- d. Have a relationship with each other; directly or through common third parties, that puts them in a position to have access to information about or influence on the Bid of another Bidder, or influence the decisions of the Procuring Entity regarding the bidding process; or
- e. The Bidder participates in more than one Bid in a bidding process. Participation by a Bidder in more than one Bid will result in the disqualification of all Bids in which the Bidder is involved. However, this does not limit the inclusion of the same subcontractor, not otherwise participating as a Bidder, in more than one Bid; or
- f. The Bidder or any of its affiliates participated as a consultant in the preparation of the design or technical specifications of the Goods, Works or Services that are the subject of the Bid; or
- g. Bidder or any of its affiliates has been hired (or is proposed to be hired) by the Procuring Entity as engineer-in-charge/ consultant for the contract.

Declaration by the Bidder regarding Qualifications

Declaration by the Bidder

In relation to my/our Bid submitted to for procurement of in response to their Notice inviting Bids No.Dated

I/We hereby declare under Section 7 of Rajasthan Transparency in Public Procurement Act, 2012, that :

1. I/We possess the necessary professional, technical, financial and managerial resources and competence required by the Bidding Document issued by the Procuring Entity;
2. I/We have fulfilled my/our obligation to pay such of the taxes payable to the Union and the State Government or any local authority as specified in the Bidding Document;
3. I/We are not insolvent, in receivership, bankrupt or being wound up, not have my/our affairs administered by a court or a judicial officer, not have my/our business activities suspended and not the subject of legal proceeding for any of the foregoing reasons;
4. I/We do not have, and our directors and officers not have, been convicted of any criminal offence related to my/our professional conduct or the making of false statements or misrepresentations as to my/our qualifications to enter into a procurement Contract within a period of three years preceding the commencement of this procurement process, or not have been otherwise disqualified pursuant to debarment proceedings;
5. I/We do not have a conflict of interest as specified in the Act, Rules and the Bidding Document, which materially affects fair competition;

Date :
Place :

Signature of bidder

Name :
Designation :
Address :

Grievance Redressal during Procurement Process

The designation and address of the **First Appellate Authority is Commissioner, JDA Jaipur.**

The designation and address of the **Second Appellate Authority is Executive Committee (E.C.), JDA Jaipur.**

(1) Filing an appeal

If any Bidder or prospective bidder is aggrieved that any decision, action or omission of the Procuring Entity is in contravention to the provisions of the Act or the Rules or the Guidelines issued there under, he may file an appeal to First Appellate Authority, as specified in the Bidding Document within a period of ten days from the date of such decision or action, omission, as the case may be, clearly giving the specific ground or grounds on which he feels aggrieved:

Provided that after the declaration of a Bidder as successful the appeal may be filed only by a Bidder who has participated in procurement proceedings:

Provided further that in case a Procuring Entity evaluates the Technical Bids before the opening of the Financial Bids, an appeal related to the matter of Financial Bids may be filed only by a Bidder whose Technical Bid is found to be acceptable.

(2) The officer to whom an appeal is filed under para (1) shall deal with the appeal as expeditiously as possible and shall Endeavour to dispose it of within thirty days from the date of the appeal.

(3) If the officer designated under para (1) fails to dispose of the appeal filed within the period specified in para (2), or if the Bidder or prospective bidder or the Procuring Entity is aggrieved by the order passed by the First Appellate Authority, the Bidder or prospective bidder or the Procuring Entity, as the case may be, may file a second appeal to Second Appellate Authority specified in the Bidding Document in this behalf within fifteen days from the expiry of the period specified in para (2) or of the date of receipt of the order passed by the First Appellate Authority, as the case may be.

(4) Appeal not to lie in certain cases

No appeal shall lie against any decision of the Procuring Entity relating to the following matters, namely:-

- (a) Determination of need of procurement;
- (b) Provisions limiting participation of Bidders in the Bid process;
- (c) The decision of whether or not to enter into negotiations;
- (d) Cancellation of a procurement process;
- (e) Applicability of the provisions of confidentiality.

(5) Form of Appeal

(a) An appeal under para (1) or (3) above shall be in the annexed form along with as many copies as there are respondents in the appeal.

(b) Every appeal shall be accompanied by an order appealed against, if any, affidavit verifying the facts stated in the appeal and proof of payment of fee.

(c) Every appeal may be presented to First Appellate Authority or Second Appellate Authority, as the case may be, in person or through registered post or authorized representative.

(6) Fee for filing appeal

(a) Fee for first appeal shall be rupees two thousand five hundred and for second appeal shall be rupees ten thousand, which shall be non-refundable.

(b) The fee shall be paid in the form of bank demand draft or banker's cheque of a Scheduled Bank in India payable in the name of Appellate Authority concerned.

(7) Procedure for disposal of appeal

(a) The First Appellate Authority or Second Appellate Authority, as the case may be, upon filing of appeal, shall issue notice accompanied by copy of appeal, affidavit and documents, if any, to the respondents and fix date of hearing.

(b) On the date fixed for hearing, the First Appellate Authority or Second Appellate Authority, as the case may be, shall,-

(i) Hear all the parties to appeal present before him; and

(ii) Peruse or inspect documents, relevant records or copies thereof relating to the matter.

(c) After hearing the parties, perusal or inspection of documents and relevant records or copies thereof relating to the matter, the Appellate Authority concerned shall pass an order in writing and provide the copy of order to the parties to appeal free of cost.

(d) The order passed under sub-clause (c) above shall also be placed on the State Public Procurement Portal.

FORM No. 1

[See Rule 83]

**Memorandum of Appeal under the Rajasthan
Transparency in Public Procurement Act, 2012**

Appeal No. of Before the
..... (First/Second Appellate Authority)

1. Particulars of appellant :

(i) Name of the appellant :

(ii) Official address, if any :

(iii) Residential address :

2. Name and address of the respondent (s) :

(i)

(ii)

(iii)

3. Number and date of the order appealed against and name and designation of the officer/authority who passed the order (enclose copy), or a statement of a decision, action or omission of the Procuring Entity in contravention to the provisions of the Act by which the appellant is aggrieved:

4. If the Appellant proposes to be represented by a representative, the name and postal address of the representative:

5. Number of affidavits and documents enclosed with the appeal :

6. Grounds of appeal :
(Supported by an affidavit)

7. Prayer :

Place

Date

Appellant's Signature

Additional Conditions of Contract**1. Correction of arithmetical errors**

Provided that a Financial Bid is substantially responsive, the Procuring Entity will correct arithmetical errors during evaluation of Financial Bids on the following basis:

- i. If there is a discrepancy between the unit price and the total price that is obtained by multiplying the unit price and quantity, the unit price shall prevail and the total price shall be corrected, unless in the opinion of the Procuring Entity there is an obvious misplacement of the decimal point in the unit price, in which case the total price as quoted shall govern and the unit price shall be corrected;
- ii. If there is an error in a total corresponding to the addition or subtraction of subtotals, the subtotals shall prevail and the total shall be corrected ; and
- iii. If there is a discrepancy between words and figures, the amount in words shall prevail, unless the amount expressed in words is related to an arithmetic error, in which case the amount in figures shall prevail subject to (i) and (ii) above.

If the Bidder that submitted the lowest evaluated Bid does not accept the correction of errors, its Bid shall be disqualified and its Bid Security shall be forfeited or its Bid Securing Declaration shall be executed.

2. Procuring Entity's Right to Vary Quantities

- (i) At the time of award of contract, the quantity of Goods, works or services originally specified in the Bidding Document may be increased or decreased by a specified percentage, but such increase or decrease shall not exceed twenty percent, of the quantity specified in the Bidding Document. It shall be without any change in the unit prices or other terms and conditions of the Bid and the conditions of contract.
- (ii) If the Procuring Entity does not procure any subject matter of procurement or procures less than the quantity specified in the Bidding Document due to change in circumstances, the Bidder shall not be entitled for any claim or compensation except otherwise provided in the Conditions of Contract.
- (iii) In case of procurement of Goods or services, additional quantity may be procured by placing a repeat order on the rates and conditions of the original order. However, the additional quantity shall not be more than 25% of the value of Goods of the original contract and shall be within one month from the date of expiry of last supply. If the supplier fails to do so, the Procuring Entity shall be free to arrange for the balance supply by limited Bidding or otherwise and the extra cost incurred shall be recovered from the supplier.

3. Dividing quantities among more than one Bidder at the time of award (In case of procurement of Goods)

As a general rule all the quantities of the subject matter of procurement shall be procured from the Bidder, whose Bid is accepted. However, when it is considered that the quantity of the subject matter of procurement to be procured is very large and it may not be in the capacity of the Bidder, whose Bid is accepted, to deliver the entire quantity or when it is considered that the subject matter of procurement to be procured is of critical and vital nature, in such cases, the quantity may be divided between the Bidder, whose Bid is accepted and the second lowest Bidder or even more Bidders in that order, in a fair, transparent and equitable manner at the rates of the Bidder, whose Bid is accepted.

Executive Engineer (PHE-II)
JDA, Jaipur

Signature of Contractor
with full address & Mobile No.

JAIPUR DEVELOPMENT AUTHORITY, JAIPUR

No. JDA/Ex.En. (TA to Dir. Engg.-I)/2016/D-29

Dated: 11/3/2016

Office Order

Subject: - DLP period for various type of works.

As per the decision taken in the 201st meeting of Executive Committee held on 23.02.2016 w.r.t. agenda no. 201:22, DLP period of various natures of works amounting more than Rs. 25 lakhs has been revised as per following time periods based on nature of works.

This order will supersede the earlier orders issued in this regard i.e. order No. JDA/TA to D(E)/2010-11/D-317 dated 28.04.2011 including Special Condition No. 2.2.2 & 2.2.3 of Annexure-I related to SD refund & forfeiture (other Special Condition of annexure-I of this order will remain valid) and order No. JDA/Ex.En.(Pr.-5 & TA)/2013/D-43 dated 27.02.2013 and also all pertaining orders, in contract agreements or in PWF&AR having DLP period different than what is being enforced through this present order for concerned type of work.

Table-I

S.No.	Type of Work	Existing DLP Period	As per approved in E.C. held on 23.02.2016
1.	Bridge Work	3 years	5 Years
2.	CD Work	3 years	5 Years
3.	CC Road, PQC Work	3 years	5 Years
4.	CC tiles/Kerbs/medians	3 years	5 years
5.	Drains	6 months	3 years
6.	Roads		
	(i) Two layer WBM/ GSB	3 years	6 Months or one full rainy season which ever is later
	(ii) For Renewal/ Strengthening		
	(a) BT upto 30 mm thickness	3 years	1 year
	(b) BT above 30 mm to upto 40 mm	3 years	2 years
	(c) BT above 40 mm to upto 90 mm	3 years	3 years
	(d) FT Above 90 mm	3 years	5 years
	(iii) New Roads		
	(a) BT upto 90 mm	3 years	3 years
	(b) BT more than 90 mm	3 years	5 years
7.	Compound wall	6 months	3 years
8.	Buildings work		
	(i) Work pertaining to Sanitary works electrical works, Joinery works and painting works.	6 months	2 years
	(ii) Work pertaining to Building structure and other civil works.	6 months	5 years
9.	Electric work except maintenance	6 months	3 years
10.	Sewer/Water supply all including STP and water supply related work except maintenance works.	6 months	3 years <i>4*</i>

The release of SD amount shall be as per following table:-

Table-II

S. No.	Released SD DLP period	1 st year	2 nd year	3 rd year	5 th year
1.	Upto 1 year	100%	40%	20% ✓	10%
2.	Upto 2 year		60%	20% ✓	10%
3.	Upto 3 year			60% ✓	10%
4.	Upto 4 year				20%
5.	Upto 5 year				50%

Various conditions for managing DLP are as under:-

- (i) At the time of completion of work, final component shall be worked out for each individual item like BT/CC/tiles/drains etc (as per different categories in Table I), DLP shall be operative based upon type of individual item ex:- CC-5 years, BT- 1/2/3/5 years, Drain- 3 years etc.
- (ii) Similarly for all new works, these components should be calculated at the time of TS itself, which should be made part of BID document.
- (iii) If any work, amount is less than Rs. 25 lakhs but later on due to extra/excess work, if amount of final work crosses more than Rs. 25 lakhs, DLP shall be operative as per rule for each individual item.
- (iv) Similarly if any work is more than Rs. 25 lakhs but after finalization amount of work is less than Rs. 25 lakhs, DLP should be operative for six months or rainy season whichever is late.
- (v) During DLP period if contractor fails to repair any work even after issue of 7 days written notice, same work shall be got executed by respective Executive Engineer at the contractor's risk and cost. This process shall be applicable throughout the DLP period. After completion of DLP period in such works contractor should be debarred and blacklisted from JDA for three years as per RTTP Rule 2012 and 2013 where he defaults twice in a single agreement or in two different works.
- (vi) Quarterly Inspection as per rules shall be carried out and DLP registers shall be maintained by respective Executive Engineers to monitor the DLP repairs.
- (vii) Special and regular inspection shall also be carried out as per order no. JDA/Ex.En & TA to DE-I/2014-15/D-223 dated 12.03.2015 and order no. SE (PMGSY) CIRCULAR 2006/D-115 dated 04.05.2006 Point no. 3.
- (viii) In case JDA feels to take up work on any existing DLP road due to any reason, following procedure should be adopted:
 - (a) At the time of withdrawal total liability of repairs as per DLP conditions to be carried out and contractor shall be asked to complete the same. After completion of assessed repairs DLP period shall be released after deduction amt. as per table III.

Table-III

% Recovery on Withdrawal of DLP, of work order DLP period	1 year	2 year	3 year	4 year	5 year
1 year	1.12	-	-	-	-
2 year	2.55	1.43	-	-	-
3 year	4.38	3.26	1.83	-	-
5 year	9	7.88	6.45	4.62	2.47

Note:- Calculation is to be done on quarterly basis.

(b) In case Contractor fails to carry out these repairs, same shall be carried out at his risk and cost. If the total amt. of such repairs works out to be more than total retained amt. of SD, same shall be recovered from other works and as per PDR rules. The amount as per Table III is also to be deducted in addition to this amount.

(ix) Based upon type of work, DLP conditions for works to be carried out during DLP period with their frequency of respective type of work shall be prepared by respective SE's after approval of these periods.

This order shall come in force with immediate effect and will be applicable on all new works whose NIB is to be called.

Sd/-
Director (Engineering-I)
JDA, Jaipur

Copy to following for information and necessary action:-

1. PS to IDC, JDA, Jaipur.
2. PS to Secretary, JDA, Jaipur.
3. Director Engineer I/II, JDA, Jaipur.
4. Director (Fin.), JDA, Jaipur.
5. C.F, JDA, Jaipur.
6. All Add. Chief Engineers, JDA, Jaipur.
7. All Superintendent Engineers, JDA, Jaipur.
8. OSD (RM), JDA, Jaipur.
9. Additional Director (REV.&DP.)
10. CAO (P&A) JDA, Jaipur.
11. Sr. Horticulturist, JDA, Jaipur
12. All Executive Engineer, JDA, Jaipur.
13. DD (E&B) JDA, Jaipur.
14. All AOs, JDA, Jaipur.
15. All AAOs, JDA, Jaipur.
16. System Analyst
17. All Contractors' Association, JDA, Jaipur.
18. Guard file

Sd/-
S.E. & TA to Dir. (Engg-I)
JDA, Jaipur

Jaipur Development Authority, Jaipur

Office Order

No. : JDA/IT(1074501)/E-Services/2015-16/D-399

Dated: 4-10-2016

Subject: Payment mechanism for participating in tender.

Jaipur Development Authority has decided to receive Earnest Money Deposit (EMD) (Bid Security), Tender Fee and RISL processing fee online through JDA Portal. The bid security options available in tender for participants are as mentioned below:

A. Payment Options:**Option-1: Bank Guarantee (BG) against EMD / Bid Security**

Bidder may opt Bank Guarantee (BG) against EMD (Bid Security), for which bidder requires to prepare BG before applying in the tender. The details of BG requires to be fed on JDA portal before paying balance amount (Tender Fee + RISL Processing Fee). This amount will be paid through **Payment Gateway only**, option to make balance payment through EFT (RTGS/NEFT) will not be available.

If bidder does not opt for BG against EMD, options of making complete payment through Payment Gateway or through EFT (NEFT / RTGS) will be available.

Option-2: Electronic Fund Transfer (EFT: NEFT/RTGS)

If the bidder selects payment mode as EFT (NEFT/RTGS), "Paying Slip for EFT (NEFT/RTGS)" will be generated by the system for the complete amount. The payment can be made from **any Bank any Branch** using this Paying Slip through NEFT/RTGS (Claim against payment made through EFT in any other JDA bank account will not be acceptable and bidder stands disqualified from participation in the bid applied for). After successful transaction through NEFT/RTGS, as per the standard procedures it may take 4 to 24 hours in process of confirmation of EFT through Auto-Process depending on the time of EFT done. Therefore, option to make payment through EFT (NEFT/RTGS) will be available till 2 days prior to closing date of bid participation.

Option-3: Payment Gateway (Aggregator)

The facility to make payment through Debit Card, Credit Card, Net banking etc., will be available. User can use this facility from **anywhere any time** till the closing date & time of bid participation.

B. Bid Participation Receipt

After confirming payment, the bidder will get Bid Participation Receipt on the basis of which user will get the payment details along with other details for bidding on e-Procurement portal of GOR.

- In case of BG as the remaining payment will be done through Payment Gateway, on successful transaction the "Bid Participation Receipt" will be generated on real time basis.

- In case complete payment is done through Payment Gateway, on successful transaction the “**Bid Participation Receipt**” will be generated on real time basis.
- In case complete payment is done through EFT (NEFT/RTGS), on confirmation of payment from ICICI Bank (Auto Process) “**Bid Participation Receipt**” will be available on Login of Bidder on JDA portal.

This payment mechanism will come into force w.e.f 15/10/2016. Thereafter, old payment mechanism related to NEFT/ RTGS in which the bidder makes direct payment without “**Paying Slip for EFT (NEFT/RTGS)**” in JDA’s bank account will be discontinued.

All procuring entities are hereby directed to clearly mention this procedure in NIB document.


(Pawan Arora)
Secretary

Copy for information and further necessary action to:

1. P.S. to JDC, JDA, Jaipur.
2. P.S. to Secretary, Secretary, JDA, Jaipur.
3. Director (Law / Finance / Town Planning / Engineering-I / Engineering-II), JDA, Jaipur.
4. All Additional Chief Engineer _____, JDA, Jaipur
5. DC (Administration)/DC(Store)/DC (Vehicle), JDA, Jaipur
6. System Analyst, JDA, Jaipur
7. Analyst-cum-Programmer, JDA to ensure integration of software w.e.f 01/10/2016.
8. All Xen _____, JDA, Jaipur.
9. Officer-in-charge, SPPP Portal, Jaipur.
10. OSD (Public Relation) / PRO, JDA, Jaipur.


(Brijesh Kishore Sharma)
OSD (RM)

जयपुर विकास प्राधिकरण, जयपुर

क्रमांक :- F-()JDA/Sr.Ao.works-II/2017/D-172

दिनांक :- 12.7.17

आदेश

1 जुलाई 2017 से भारत सरकार के नोटिफिकेशन द्वारा GST लागू होने के कारण व्यक्तियों/फर्मो/कम्पनी/संस्था/टेकेदार के निर्माण/सिविल आपूर्ति/सेवाओं इत्यादि के कार्यों के प्राधिकरण द्वारा बिल भुगतान किये जाने के लिये प्राधिकरण कर सलाहकार चार्टर्ड एकाउन्टेन्ट से प्राप्त हुई राय के क्रम में निम्नांकित प्रमाण पत्र/शपथ पत्र/Invoice बिलों के साथ प्रस्तुत किया जाना सुनिश्चित करावे :-

- व्यक्ति/फर्म/कम्पनी/संस्था/टेकेदार का GST के अन्तर्गत रजिस्ट्रेशन प्रमाण पत्र की स्व:प्रमाणित फोटो प्रति।
- व्यक्ति/फर्म/कम्पनी/संस्था/टेकेदार का GST के रजिस्ट्रेशन नहीं होने के स्थिति में स्व:प्रमाणित शपथ पत्र।
- अप्राप्त व्यक्तित्व/फर्म/कम्पनी/संस्था/टेकेदार के बिलों के भुगतान की स्थिति में मासिक टैक्स Invoice भुगतान-अधिकारी द्वारा मासिक आधार पर उसी माह के अंत में तैयार करवाया जाना सुनिश्चित किया जावेगा।
- आपूर्ति एवं सेवा के विरुद्ध भुगतान बिलों में Vat/Service Tax चार्ज होने (Vat/Service Tax होने) पर (दिनांक 30.06.17 तक आपूर्ति एवं Invoice जारी करने पर) Taxable Invoice नहीं बनाया जावेगा एवं इनका भुगतान पूर्वानुसार (01.07.2017 से पूर्व निहित प्रक्रिया अनुसार) किया जाना सुनिश्चित करावे।

स्पष्टीकरण :- दिनांक 30.06.17 तक सामान की आपूर्ति के बिलों में Vat Invoice होने पर या अन्यथा होने पर इनका भुगतान पूर्वानुसार 01.07.2017 से पूर्व निहित प्रक्रिया अनुसार किया जावेगा।

संलग्न :- GST रेट तथा HSN/SAC CODE की फोटो प्रति

(बृजेश किशोर शर्मा)
निदेशक(वित्त)

प्रतिलिपि निम्न को सूचनार्थ एवं आवश्यक कार्यवाही हेतु :-

- वॉरंट निजी सचिव, आयुक्त, जविप्रा, जयपुर।
- वॉरंट निजी सचिव, सचिव, जविप्रा, जयपुर।
- निदेशक (वित्त/विवि/अभियंत्रिकी-प्रथम व द्वितीय/आयोजना/परियोजना, जविप्रा, जयपुर।
- अतिरिक्त आयुक्त(प्रशासन/पूर्व/पश्चिम/एल.पी.सी./भूमि), जविप्रा, जयपुर।
- संयुक्त आयुक्त(सिस्टम मैनेजमेन्ट/संसाधन एवं समन्वय), जविप्रा, जयपुर।
- विशेषाधिकारी(संसाधन विकास), जविप्रा, जयपुर।
- अतिरिक्त निदेशक(राजस्व एवं सम्पत्ति निस्तारण), जविप्रा, जयपुर।
- समस्त जोन उपायुक्तगण, जविप्रा, जयपुर।
- मुख्य लेखाधिकारी(पी. एण्ड ए.), जविप्रा, जयपुर।
- उपनिदेशक(व्यय एवं बजट), जविप्रा, जयपुर।
- वरिष्ठ लेखाधिकारी(निर्माण-प्रथम/द्वितीय/आर.सी.आर./पेंशन/नीलामी), जविप्रा, जयपुर।
- सिस्टम एनालिस्ट, जविप्रा, जयपुर को प्रेषित कर लेख है कि सिस्टम में GST नम्बर सम्मिलित करने एवं Tax Invoice बनाने की प्रक्रिया तैयार करावे
- उप रजिस्ट्रार(सहकारिता), जविप्रा, जयपुर।
- अधिशोषी अभियन्ता जोन, जविप्रा, जयपुर।
- वरिष्ठ उद्यानविज्ञ, जविप्रा, जयपुर।
- लेखाधिकारी (भुगतान/योजना/निर्माण)/सहायक लेखाधिकारी, जविप्रा, जयपुर।
- प्रभारी अधिकारी, नागरिक सेवाकेन्द्र, जविप्रा, जयपुर।
- सलाहकार(जनसम्पर्क), जविप्रा, जयपुर।
- रोकडिया(निर्माण/सिविल/भूमि आवापति), जविप्रा, जयपुर।
- रक्षित पत्रावली

अति.निदेशक(रा.एवं स.नि.)



	राजस्थान राजपत्र	RAJASTHAN GAZETTE
	विशेषांक	Extraordinary
	साधिकार प्रकाशित	Published by Authority
	आश्विन 30, शुक्रवार, शाके 1943-अक्टूबर 22, 2021 <i>Asvina 30, Friday, Saka 1943- October 22, 2021</i>	

भाग 4 (ग)

उप-खण्ड (I)

राज्य सरकार तथा अन्य राज्य-प्राधिकारियों द्वारा जारी किये गये (सामान्य आदेशों, उप-विधियों आदि को सम्मिलित करते हुए) सामान्य कानूनी नियम।

FINANCE (G&T) DEPARTMENT

NOTIFICATION

Jaipur, October 22, 2021

G.S.R.364 .-In exercise of the powers conferred by section 55 of the Rajasthan Transparency in Public Procurement Act, 2012 (Act No. 21 of 2012), the State Government hereby makes the following rules further to amend the Rajasthan Transparency in Public Procurement Rules, 2013, namely:-

1. Short title and commencement.- (1) These rules may be called the Rajasthan Transparency in Public Procurement (Fourth Amendment) Rules, 2021.

(2) They shall come into force from the date of their publication in the Official Gazette.

2. Insertion of new rule 75A.- After the existing rule 75 and before the existing rule 76 of the Rajasthan Transparency in Public Procurement Rules, 2013, the following new rule 75A shall be inserted, namely:-

"75A. Additional Performance Security.- (1) In addition to Performance Security as specified in rule 75, an Additional Performance Security shall also be taken from the successful bidder in case of unbalanced bid. The Additional Performance Security shall be equal to fifty percent of Unbalanced Bid Amount. The Additional Performance Security shall be deposited in lump sum by the successful bidder before execution of Agreement. The Additional Performance Security shall be deposited through e-Grass, Demand Draft, Banker's Cheque, Government Securities or Bank Guarantee.

Explanation : For the purpose of this rule,-

- Unbalanced Bid means any bid below more than fifteen percent of Estimated Bid Value.
- Estimated Bid Value means value of subject matter of procurement mention in bidding documents by the Procuring Entity.
- Unbalanced Bid Amount means positive difference of eighty five percent of Estimated Bid Value minus Bid Amount Quoted by the bidder.



(2) The Additional Performance Security shall be refunded to the contractor after satisfactory completion of the entire work. The Additional Performance Security shall be forfeited by the Procuring Entity when work is not completed within stipulated period by the contractor. Provision for 'Unbalanced Bid' and 'Additional Performance Security' shall be mentioned in the Bidding Documents by the Procuring Entity."

[No. F.2(1)FD/G&T(SPFC)/2017]
By Order of the Governor,

Vimal Kumar Gupta,
Joint Secretary to the Government.

राज्य केन्द्रीय मुद्रणालय, जयपुर।



जयपुर विकास प्राधिकरण, जयपुर

www.jda.urban.rajabasthan.gov.in

क्रमांक जविप्रा/अधि. अभि./त.स.नि.अ.-1/2021/डी-75

दिनांक :- 26/8/2021

To

Contractor's Association
Jaipur Development Authority
Jaipur.

जयपुर विकास प्राधिकरण में विभिन्न कार्यों हेतु कार्यों की प्रकृति के अनुसार निविदाएँ, कार्यालय आदेश क्रमांक JDA/Ex.En. (TA to Dir.Engg.-I)/2014-15/D-202 Dated:16.02.2015 द्वारा एकल बिड व Two bid में invite की जाती है। निविदाएँ प्राधिकरण की EC द्वारा अनुमोदित निविदा दस्तावेज के अनुसार की जाती है। निविदाओं के evaluation के दौरान प्रायः यह देखा जाता है कि निविदाकर्ता द्वारा निविदा प्रपत्र में अंकित दिशानिर्देशों के अनुसार प्रस्तुत किए गये आवश्यक दस्तावेज या तो अधूरे होते हैं या चाहे गये प्रफोर्मा प्रपत्र के अनुसार नहीं आयेदित किए जाते हैं। इस कारण से कई बार निविदाएं छोटी-छोटी गलतियों की वजह से निरस्त हो जाती है या Particular bidder disqualify हो जाते हैं। कुछ सामान्य गलतियाँ निम्नानुसार हैं:-

1. Schedule 1 to 4 को नहीं भरना।
2. RTPP प्रपत्र A,B,C,D को नहीं भरना व हस्ताक्षर नहीं करना।
3. निविदा दस्तावेज विभिन्न दस्तावेजों पर स्वयं के या नोटेरी के हस्ताक्षर नहीं होना।
4. रजिस्ट्रेशन की प्रति नहीं लगाना।
5. EMD Receipt नहीं लगाना।
6. Work performance certificate नहीं लगाना।
7. Non Judicial Stamp पर दी जाने वाली सूचनाएं सामान्य प्रष्ठ पर देना।
8. Two bid निविदाओं में वर्ष वार कार्य की मात्राएं एवं राशि नहीं देना।
9. अनावश्यक दस्तावेज उपलब्ध कराना।
10. Online bidding के लिए आवश्यक विभिन्न शुल्क जमा नहीं कराना।
11. GST Clearance Certificate नहीं लगा होना।
12. Certificate having quantities financial year wise should not be missing.
13. Certificate of maximum value of similar nature work executed in any one last financial year out of last five financial year.
14. Annual turn over certificate by CA नहीं लगाना।
15. मशीनरी की details संलग्न नहीं करना।
16. Bid Fee, Bid Processing Fee, Tax Clearance Certificate should not be missing.
17. Completion certificate of required similar nature component is to be enclosed.
18. Litigation History Should be enclosed.
19. Information regarding existing commitments and ongoing works should be enclosed.

इस सम्वन्ध में सभी निविदाताओं को सूचित किया जाता है कि निविदाएं जमा करने से पहले निविदा प्रपत्र में अंकित व चाहि गयी सूचनाएं उचित तरीके से भर कर ही निविदा प्रस्तुत करे जिससे अनावश्यक रूप से निविदा निरस्तीकरण से बचा जा सके। त्रुटीपूर्ण निविदा की स्थिति में निविदाता स्वयं ही जिम्मेदार होंगे।

(31/8)
अधीक्षण अभियन्ता एवं
तक.सहा. निदे. (अभि.-प्रथम)
जविप्रा, जयपुर

रामकिशोरव्यासभवन, इन्दिरासर्किल, जवाहरलालनेहरूमार्ग, जयपुर-302004

दूरभाष :- ईपीबीएक्स - +91-141-2569696 एक्सटेंशन: (7209); फ़ैक्स- +91-141-2574555

e-Mail : (sudhirsharma.jda@rajasthan.gov.in)

Scanned with CamScanner



जयपुर विकास प्राधिकरण, जयपुर

www.jda.urban.rajasthan.gov.in

क्रमांक जविप्रा/अधि. अभि./त.स.नि.अ.-1/2021/डी-75

दिनांक :- 26/8/2021

प्रतिलिपि निम्न को सूचनार्थ एवं आवश्यक कार्यवाही हेतु प्रेषित है:-

1. निजी सचिव, आयुक्त, जविप्रा, जयपुर।
2. निजी सचिव, सचिव, जविप्रा, जयपुर।
3. निदेशक (अभियांत्रिकी-प्रथम/द्वितीय/वित्त), जविप्रा, जयपुर।
4. समस्त अतिरिक्त मुख्य अभियन्ता, जविप्रा, जयपुर।
5. समस्त अधीक्षण अभियन्ता, जविप्रा, जयपुर।
6. समस्त अधिशासी अभियन्ता, जविप्रा, जयपुर।
7. रक्षित पत्रावली।


अधिशासी अभियन्ता एवं
तक.सहा. निदे. (अभि.-प्रथम)
जविप्रा, जयपुर

रामकिशोरव्यासभवन, इन्दिरासर्किल, जवाहरलालनेहरुमार्ग, जयपुर-302004

दूरभाष- : ईपीबीएक्स - +91-141-2569696 एक्सटेंशन: {7209}; फैक्स- +91-141-2574555

e-Mail : {sudhirsharma.jda@rajasthan.gov.in}

Scanned with CamScanner

	राजस्थान राजपत्र	RAJASTHAN GAZETTE
	विशेषांक	Extraordinary
	साधिकार प्रकाशित	Published by Authority
	पौष 22, बुधवार, शाके 1943-जनवरी 12, 2022 <i>Pousa 22, Wednesday, Saka 1943- January 12, 2022</i>	

भाग 4 (ग)

उप-खण्ड (1)

राज्य सरकार तथा अन्य राज्य-प्राधिकारियों द्वारा जारी किये गये (सामान्य आदेशों, उप-विधियों आदि को सम्मिलित करते हुए) सामान्य कानूनी नियम।

FINANCE (G&T) DEPARTMENT

NOTIFICATION

Jaipur, January 12, 2022

G.S.R.398 .-In exercise of the powers conferred by section 55 of the Rajasthan Transparency in Public Procurement Act, 2012 (Act No. 21 of 2012), the State Government hereby makes the following rules further to amend the Rajasthan Transparency in Public Procurement Rules, 2013, namely:-

1. Short title and commencement.- (1) These rules may be called the Rajasthan Transparency in Public Procurement (Amendment) Rules, 2022.
(2) They shall come into force from the date of their publication in the Official Gazette.

2. Amendment of rule 75.- In rule 75 of the said rules,-

- (i) in proviso to sub-rule (2), for the existing expression "31.12.2021", the expression "31.03.2023" shall be substituted; and
- (ii) in proviso to clause (f) of sub-rule (3), for the existing expression "31.12.2021", the expression "31.03.2023" shall be substituted.

[No. F.2(1)FD/G&T(SPFC)/2017]

By Order of the Governor,

Vimal Kumar Gupta,
Joint Secretary to the Government.

1936

Government Central Press, Jaipur.



JAIPUR DEVELOPMENT AUTHORITY, JAIPUR

www.jda.urban.rajasthan.gov.in

No. JDA/ E.E. & (TA to Dir. Engg.-I)/2022/D-194

Dated: - 6/9/2022

Office Order

In the standard bid document (Two bid system) of JDA, Clause 5: Rejection of Bids, subclause (iii) shall be replaced and read as under with immediate effect:-

S.N.	Provision as per standard Bid document	As per GoR orders F.8(15)Fin/SPFC/2020 dated 17.05.2022
1.	"If all the copies enclosed in support and affidavit is not duly attested by notary public/gazetted officer/Self (as per order No F 14(22)JDA/Estt./2014 Dated 01.01.2015) then bid of the bidder is to be rejected."	The Bidder shall prepare bid in the digital/electronic mode for uploading on e-Procurement portal in the format/type of file specified in evaluation and Qualification criteria 'All the documents uploaded, should be digitally signed with the DSC of authorized signatory, deemed as all the pages of the uploaded documents are signed'.

The following additional condition should be added in the standard Bid document (Two Bid system)

1. The Affidavits and Annexure 'B': be enclosed by the bidder regarding Qualification of RTPP Act-2012 & Rule-2013 along with Bid document, should be signed by the participating bidders before uploading the tender document otherwise the Bid of the bidder will be rejected.
2. In case of single Bid system Annexure 'B': be enclosed by the bidder regarding Qualification of RTPP Act-2012 & Rule-2013 along with Bid document, should be signed by the participating bidders before uploading the tender document otherwise the Bid of the bidder will be rejected.

This will be enforced with immediate effect.


Director Engineering-I
JDA, Jaipur

Copy to:-

1. Director (Engineering-I/II/III/IV), JDA, Jaipur.
2. Director (Finance), JDA, Jaipur.
3. C.F. JDA, Jaipur.
4. All Additional Chief Engineers, JDA, Jaipur.
5. All Superintending Engineers, JDA, Jaipur.
6. All Executive Engineers, JDA, Jaipur for include this in every bid instead of previous condition.
7. O.S.D. (RM)/A.D.R. , JDA, Jaipur.
8. Sr. Horticulture, JDA, Jaipur.
9. Sr. A.O., JDA, Jaipur.


Director Engineering-I
JDA, Jaipur

C:\Users\Admin\Desktop\Office Order Letter Head-English UO Note 2022.docx

Ram Kishor Vyas Bhawan, Indira Circle, Jawahar Lal Nehru Marg, Jaipur-302004
Direct Line- {+91-141-2563234} : EPABX - +91-141-2569696 Extn : {7203} : Fax - +91-141-2574555

Scanned with CamScanner

SPECIAL CONDITIONS

1. If there is any typographical error or otherwise in the 'G' Schedule the rates given in the relevant BSR on which schedule 'G' has been prepared, shall prevail.
2. The contractor shall follow the contractor labour regulation and abolition Act 1970 & Rule 1971.
3. The JDA shall have right to cause on audit and technical examination of the work and the final bills of the contractor including all supporting vouchers, abstract etc. to be made within two years after payment of the final bills and if as a result such audit any amount is found to have been over paid/excess in respect of any work done by the contractor under the contract or any work claimed by him to have been done under this contract and found not to have been executed the contractor shall be liable to refund such amount and it shall be lawful ;for the JDA to recover such sum from him in ;the manner prescribed in special condition no. 8 or any other manner legally permissible and if it is found that the contractor was paid less than that was due to him under the contract in respect of any work executed by him under it, the amount of such under payment shall be paid by the JDA to the contractor.
4. The contractor shall not work after the sunset and before sunrise without specific permission of the authority Engineer.
5. Whenever any claim against the contractor for the payment of a sum of money arises out or under the contracts, the JDA shall be entered to recover the sum by appropriating in part or whole of the security deposit of the contractor. In the event of the security being insufficient or if no security has been taken from the contractor then the balance of the total sum recoverable as the case may shall be deducted from any sum then due or which a any time there contract with the JDA should this sum be sufficient to recover the full amount recoverable, the contractor shall pay to JDA on demand the balance remaining due. The JDA shall further have the right to effect such recoveries under P.D.R. Act.
6. The rate quoted by the contractor shall remain valid for a period of 120 days from the date of opening of the tenders.
7. By submission of this tender the contractor agree to abide with all printed conditions provided in the PWD manual from 64 (Chapter 3-para 36) and subsequent modification.
8. No conditions are to be added by the contractor and conditional tender is liable to be rejected.
9. All transaction in the execution of this work and this tender will be liable to sale-tax vide section 2(B) read with sub clause (4) Sale-tax Rule, 1954.
10. If any Bid withdraws his Bid prior to expiry of said validity period given at S.No. 6 or mutually extended prior or makes modifications in the rates, terms and conditions of the tender within the said period which are not acceptable to the department or fails to commence the work in the specified period, fails to execute the agreement and fails to furnish performance guarantee the department shall without prejudice to any, other right or remedy, be at liberty to forfeit the amount of earnest money given in any form absolutely. If any contractor, who having submitted a Bid does not execute the agreement or start the work or dose not complete the work and the work has to be put to re-biding, he shall stand debarred from participating in bidding in JDA for Six Months in addition to forfeiture of Earnest Money / Security Deposit /Performance Guarantee and other action under agreement
11. Rules regarding enlistment of contractors provide that work up to five times limit for which they are qualified for tendering can be allotted to them. Therefore, before tender the contractors will keep this in mind, and submit the details of work. Bids with incomplete or incorrect information are liable to be rejected.
12. Any material not conforming to the specifications collected at site shall have to be removed by the contractor within a period of 3 days of the instructions, issued by the Engineer-In charge in writing. Failing which, such material shall be removed by the Engineer-In charge at risk and the contractor after expiry of 3 days period.
13. The material collected at site and paid provisionally shall remain under the watch and ward of the contractor till it is consumed, fully on the work.
14. The rates provided in Bid documents are inclusive of all Taxes, royalty & GST etc.
15. No extra lead of earth/material shall be paid over and above as specified in 'G' schedule. Source/borrow pit area for earth shall have to be arranged by the Contractor at his own cost.

16. Undersigned has full right to reject any or all Bids without given any reasons.
17. Mortar of Masonry work and lean concrete will be permitted mixer with hopper.
18. As per Supreme Court decision "All contracts with Governments shall require registration of workers under the building and other construction workers (Regulation of Employment and Conditions of Service) Act, 1996 and extension of benefits to such workers under the act."
19. The Bidder are required to submit copy of their enlistment as contractor.
20. Conditions of RPWA-100 will be mandatory & acceptable to the contractor.
21. Any Bid received with unattested cutting/overwriting in rates shall be rejected and such bidder will be debarred from Bidding for **three months** in JDA.
22. All the provisions of THE RAJASTHAN TRANSPARENCY IN PUBLIC PROCUREMENT ACT, 2012 and Rules, 2013 will be applicable. If there is any contradictions in existing special conditions and provisions of THE RAJASTHAN TRANSPARENCY IN PUBLIC PROCUREMENT ACT, 2012 and RULES, 2013 shall be applicable.

Signature of Contractor
With full address & Mobile No.

Executive Engineer (PHE-II)
JDA, Jaipur

Section A-6

Drawings





NOTE FOR M.H. COVER:-


1. ALL DIMENSIONS ARE IN MM.
2. ALL REINFORCEMENT BARS TO BE RIBBED FOR STEEL CONFORMING IS 16-1786
3. SHOWS THE DIRECTION OF FLOW.
4. EXPOSED PORTION OF C.I. OR STEEL SHALL BE PAINTED WITH ANTI CORROSSIVE BITUMENSINIC PAINT.
5. BOTTOM OF THE COVER SHALL BE PAINTED WITH ANTI CORROSSIVE BITUMENSINIC PAINT.
6. COVERS SHALL BE ABLE TO WITH STAND THE TEST LOAD AS PER C.I. OR STEEL THAT IS 15-1726. TESTING OF COVERS SHALL BE DONE ON CONCRETE OR AN AREA OF 100MM DIA. SAT. UNFACTURE LOAD AND ULTIMATE ROAD 22MT.
7. FINISHING OF CASTINGS OF COVER AND FRAME RING SHALL BE DONE BY SAND BLASTING.
8. MINIMUM WEIGHT OF C.I. FRAME SHALL BE 18KG. MINIMUM WEIGHT OF C.I. RIM PART OF COVER SHALL BE 15KG.
9. LIFTING COP SHALL BE OF MINIMUM 4MM THICK. MS PLATE DIA OF LIFTING BAR SHALL BE 16MM.

NOTE FOR FOOT STEPS:-


1. THE FOOT STEPS SHALL BE TESTED FOR UN-FACTURE LOAD OF 225KG AND ULTIMATE LOAD OF 1MT.
2. THE FOOT STEPS SHALL BE MANUFACTURED BY MICRO PRESSING METHOD AND AS PER DETAILED SPECIFICATIONS.



PLAN OF FERRO CEMENT COVER



DETAIL AT A-A



SECTION AT 1-1


CLIENT	JAIPUR DEVELOPMENT AUTHORITY
PROJECT	FOR SEWER NETWORK IN NORTH-WEST PART OF JAIPUR UNDER JNNURM
DES. TITLE	DETAIL OF FERROCEMENT COVER WITH C.I. FRAME & RING
DRAWN BY	SCALE 1:1
DATE	10/01/2018

TRENCH EXCAVATION FOR SEWER


S.NO.	SIZE OF PIPE (LD)	B	H	C
1	150 (S.W.)	500	100	750
2	200 (S.W.)	632	100	750
3	250 (RCC)	630	100	750
4	300 (RCC)	500	100	750
5	350 (RCC)	500	100	750
6	400 (RCC)	614	100	750
7	450 (RCC)	664	100	800
8	500 (RCC)	720	115	850
9	600 (RCC)	770	125	900
10	700 (RCC)	860	175	1100
11	800 (RCC)	1115	200	1400
12	900 (RCC)	1250	225	1500
13	1000 (RCC)	1390	250	1600
14	1100 (RCC)	1525	275	1700
15	1200 (RCC)	1665	300	1800
16	1400 (RCC)	1940	350	2050

CONSTRUCTIONAL DETAILS FOR RCC NP2 CLASS PIPES

S.NO.	D	Bc	Bt	B	H	Ht	Value of x for various Invert depth												
							1.0	1.5	2.0	2.5	3.0	3.5	4.0	4.5	5.0	5.5	6.0	6.5	7.0
1	150	200	750	580	100	45	0	0	0	0	0	0	0	0	0	0	0	0	0
2	200	250	750	450	100	65	0	0	0	0	0	0	0	0	0	0	0	0	0
3	250	300	750	500	100	75	0	0	0	0	0	0	0	0	0	0	0	0	0
4	300	360	750	560	100	90	0	0	0	0	0	0	0	0	0	0	0	0	0
5	350	414	750	614	100	105	0	0	0	0	0	0	0	0	0	0	0	0	0
6	400	464	800	664	100	120	0	0	0	0	0	0	0	0	0	0	0	0	0
7	450	520	850	720	115	130	0	0	0	0	0	0	0	0	0	0	0	0	0
8	500	570	900	770	125	145	0	0	0	0	0	0	0	0	0	0	0	0	0
9	600	690	1100	880	150	170	0	0	0	0	0	0	0	0	0	0	0	0	0
10	700	800	1200	980	175	195	0	0	0	0	0	0	0	0	0	0	0	0	0
11	800	900	1400	1115	200	225	0	0	0	0	0	0	0	0	0	0	0	0	0
12	900	1010	1500	1250	225	250	0	0	0	0	0	0	0	0	0	0	0	0	0
13	1000	1120	1600	1390	250	280	0	0	0	0	0	0	0	0	0	0	0	0	0
14	1100	1230	1700	1525	275	305	0	0	0	0	0	0	0	0	0	0	0	0	0
15	1200	1340	1800	1665	300	335	0	0	0	0	0	0	0	0	0	0	0	0	0
16	1400	1550	2050	1940	350	390	0	0	0	0	0	0	0	0	0	0	0	0	0



DETAIL OF TRENCH EXCAVATION



PLAIN CEMENT CONCRETE CRADLE BED AND ENCASING OF RCC PIPES

Scanned by CamScanner

JAI PUR DEVELOPMENT AUTHORITY	
SUBJECT FOR SEWER NETWORK IN NORTH-WEST PART OF JAI PUR UNDER JNNURM	
DETAILS FOR TRENCH EXCAVATION, CRADLE CONCRETING AND RCC PIPE ENCASING	
DATE: 10/01/2017	SCALE: 1:100
DESIGNER: JAI PUR DEVELOPMENT AUTHORITY	DATE: 10/01/2017

Section A-7

Bill of Quantities

JAIPUR DEVELOPMENT AUTHORITY, JAIPUR

Name of work:- Rate contract for two years for Providing Laying and Jointing of sewer lines with manholes under PHE-II Jurisdiction, JDA, Jaipur..

G-Schedule

BSR- 2016 JDA BSR (Building Works)/(General Basic Rates)/JDA BSR (Sanitary Works)/JDA PHE BSR (Sewerage & Water Supply)

S. NO.	Particulars	Unit	Qty.	Rate (In Rs.)	Amount (In Rs.)
1	Providing, laying and jointing of 200 mm diameter full round HDPE DWC (double wall corrugated) pipes of SN8 grade as per IS 16098 (Part 2) amended upto date in trenches with providing & laying 10 cm thick and 63 cm wide granular bedding with graded hard crusher broken stone aggregate 20 mm (nominal size) bedding in complete including all material, labour, hydraulic testing of sewer line including cost of water and equipment required for testing & commissioning as per Technical Specifications, drawings and as per direction of Engineer. The work includes earth work in all type of soil such as murrum, sand, sandy silt, black cotton soil, hard soil, kankar etc. including disposing off surplus excavated material within a lead of 50 meter including cost of close timbering beyond 1.50 meter average invert depth, shoring and strutting and refilling of trenches with excavated material, watering and ramming in layers as per PWD specifications complete in all respect and as per direction of Engineer-in-charge for following average invert depths:				
1.1	At av. Depth 0.9 meter [From 0.90 m to 1.19 m]	Mtr.	824.00	564.00	464736.00
1.2	At av. Depth 1.2 meter [From 1.20 m to 1.49 m]	Mtr.	1211.00	589.00	713279.00
1.3	At av. Depth 1.5 meter [From 1.50 m to 1.79 m]	Mtr.	1250.00	613.00	766250.00
1.4	At av. Depth 1.8 meter [From 1.80 m to 2.09 m]	Mtr.	1256.00	818.00	1027408.00
1.5	At av. Depth 2.1 meter [From 2.10 m to 2.39 m]	Mtr.	1100.00	872.00	959200.00
1.6	At av. Depth 2.4 meter [From 2.40 m to 2.69 m]	Mtr.	892.07	937.00	835869.59

S. NO.	Particulars	Unit	Qty.	Rate (In Rs.)	Amount (In Rs.)
2	Providing, laying and jointing of 200 mm diameter RCC S&S NP-4 pipes ISI Marked conforming to IS:458:1988 (Amended up to date) with anticorrosive bitumenastic paint of approved brand (2 or more coats) and make shalimar or equivalent) with ISI marked rubber ring/gasket lubricant etc including P/I 10 cm thick and 46 cm wide granular bedding with graded hard crusher broken stone aggregate 20 mm (nominal size) bedding and haunching upto 1/4 of outer diameter of pipe of sewer and laying RCC S&S pipes confirming to IS: 783: 1995 (Amended up to date) with hydraulic testing of sewer line including cost of water and equipment required for testing. The work includes earth work in all type of soil such as murrum, sand, sandy silt, black cotton soil, hard soil, kankar etc. including disposing off surplus excavated material within a lead of 50 meter including cost of close timbering beyond 1.50 meter average invert depth, shoring and strutting and refilling of trenches with excavated material, watering and ramming in layers as per PWD specifications complete in all respect and as per direction of Engineer-in-charge for following average invert depths:				
2.1	At av. Depth 3.0 meter [From 3.00 m to 3.29 m]	Mtr.	140.00	731.00	102340.00
2.2	At av. Depth 3.3 meter [From 3.30 m to 3.59 m]	Mtr.	140.00	800.00	112000.00
2.3	At av. Depth 3.6 meter [From 3.60 m to 3.89 m]	Mtr.	140.00	834.00	116760.00
2.4	At av. Depth 3.9 meter [From 3.90 m to 4.19 m]	Mtr.	140.00	879.00	123060.00
3	Providing at site, lowering & laying in trenches, aligning & jointing of 250 mm dia RCC pipes NP3 class (with s/s ends) IS: 458 - 2021 (amended up to date) marked and manufactured through vertical/vibrated casting process at all depths with Rubber gaskets (EPDM/SBR) for sewer lines as per IS: 5382 (including cost of Rubber gaskets, lubricants) as per drawing, sectional hydro testing of the sewer pipe line (including cost and conveyance of water to site for testing) etc., complete as per specification and / or as directed by Engineer. Note : E/w to be measured and paid separately.	Per Meter	320.00	826.00	264320.00

S. NO.	Particulars	Unit	Qty.	Rate (In Rs.)	Amount (In Rs.)
4	Providing, fixing and constructing of pre-cast RCC M-40 grade circular manholes with internal dia 1.0m and up to specified depth having pre-cast RCC M-40 grade circular manhole cover frame (ID 0.56m, OD 0.86m, height 0.20m), conical piece (top ID 0.56m, bottom ID 1.0m, vertical height 0.605m, wall thickness 125mm), having steel reinforcement in all pieces of manhole @ not less than 80 kg per cum of concrete. The work includes laying of 150mm thick plain cement concrete 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 20 mm nominal size) 1600 mm dia bedding in foundation, providing and laying of plain cement concrete 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate) in channel & circular starter base wall up to 50 mm above outer dia of sewer pipe and the work includes P&F pre-cast reinforced cement concrete eccentric conical piece fitted with heavy duty SFRC ring & cover and fixing of Ferro-cement foot steps and sealing of all joints with cement mortar 1:1 complete job as per detailed specifications, drawings and directions of Engineer-In charge. Note:- Excavation of earth work and road cutting for manhole will be measured and paid separately.	Each	180.00	9451.00	1701180.00
5	Providing, fixing and constructing of pre-cast RCC M-40 grade circular manholes with internal dia 1.2m and up to specified depth having pre-cast RCC M-40 grade circular manhole cover frame (ID 0.56m, OD 0.86m, height 0.20m), conical piece (top ID 0.56m, bottom ID 1.2m, vertical height 0.805m, wall thickness 125mm) having steel reinforcement in all pieces of manhole @ not less than 80 kg per cum of concrete. The work includes laying of 150mm thick plain cement concrete 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 20 mm nominal size) 1800 mm dia bedding in foundation, providing and laying of plain cement concrete 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate) in channel & circular starter base wall up to 50 mm above outer dia of sewer pipe and the work includes P&F pre-cast reinforced cement concrete eccentric conical piece fitted with heavy duty SFRC ring & cover and fixing of Ferro-cement foot steps and sealing of all joints with cement mortar 1:1 complete job as per detailed specifications, drawings and directions of Engineer-In charge. Note:- Excavation of earth work and road cutting for manhole will be measured and paid separately.	Each	207.00	12803.00	2650221.00

S. NO.	Particulars	Unit	Qty.	Rate (In Rs.)	Amount (In Rs.)
6	Providing, fixing and constructing of pre-cast RCC M-40 grade Each circular manholes with internal dia 1.5m and up to specified depth having pre-cast RCC M-40 grade circular manhole cover frame (ID 0.56m, OD 0.86m, height 0.20m), conical piece (top ID 0.56m, bottom ID 1.5m, vertical height 1.105m, wall thickness 125mm) having steel reinforcement in all pieces of manhole @ not less than 80 kg per cum of concrete. The work includes laying of 150mm thick plain cement concrete 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 20 mm nominal size) 2100 mm dia bedding in foundation, providing and laying of plain cement concrete 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate) in channel & circular starter base wall up to 50 mm above outer dia of sewer pipe and the work includes P&F pre-cast reinforced cement concrete eccentric conical piece fitted with heavy duty SFRC ring & cover and fixing of Ferro-cement foot steps and sealing of all joints with cement mortar 1:1 complete job as per detailed specifications, drawings and directions of Engineer-In charge. Note:- Excavation of earth work and road cutting for manhole will be measured and paid separately.	Each	44.00	17946.00	789624.00
7	Providing and fixing pre-cast RCC M-40 grade circular ring of dia 1.0m, height 300/225/150mm as per drawing and direction of Engineer.	Per Mtr.	118.00	5492.00	648056.00
8	Providing and fixing pre-cast RCC M-40 grade circular ring of dia 1.2m, height 300/225/150mm as per drawing and direction of Engineer.	Per Mtr.	290.00	6790.00	1969100.00
9	Providing and fixing pre-cast RCC M-40 grade circular ring of dia 1.5m, height 300/225/ 150 mm as per drawing and direction of Engineer.	Per Mtr.	125.00	8541.00	1067625.00
10	Labour charges for making connection of sewer line through manhole.	Each	1750.00	340.20	595350.00
11	Providing and fixing unplasticized Poly-Vinyl-Chloride uPVC SWR Pipes Type "B" for Sciland waste discharge system (IS:13592:1992 marked) of approved quality/make size 110 mm diameter.	Mtr.	10400.00	198.00	2059200.00
12	Providing and fixing unplasticized Poly-Vinyl-Chloride uPVC SWR Pipes fittings Type "B" for Sciland waste discharge system (IS:13592:1992 marked) of approved quality/make size 110 mm diameter (socket plug).	Each	1750.00	43.20	75600.00

S. NO.	Particulars	Unit	Qty.	Rate (In Rs.)	Amount (In Rs.)
13	Excavating trenches of required width for pipe cables, etc. inclu All kinds of soil each deposited layer by ramming, watering etc. and disposal of All kinds of soil. Pipes cables, etc. exceeding 80mm dia but not exceeding 300mm dia.	R.Mtr	10200.00	117.00	1193400.00
14	Barricading with sal ballies as per design including tying with vertical posts by coconut strings complete in all respect with two row horizontal members height 1.2 meter upto 1.5 meter above G.L. and vertical support upto 2.5 meter above C/C and for 3 days period including removal and cleaning the site complete in all respects & including dressing of sides in all types of soil. (Hire charges subsequent days (per day)).	Mt Per Day	15700.20	14.85	233147.97
15	P & F Close timbering in trenches including strutting, shoring and packing cavities (wherever required) etc. Complete (Measurement to be taken of the face area timbered):				
15.1	Depth not exceeding 1.5 Mtr.	Sqm	960.00	59.40	57024.00
15.2	Depth exceeding 1.5 Mtr. but not exceeding 3 Mtr	Sqm	960.00	62.10	59616.00
15.3	Depth exceeding 3 Mtr. but not exceeding 4.5 Mtr	Sqm	384.00	68.40	26265.60
16	Earth work in excavation by mechanical means (Hydraulic Excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including taking out the excavated soil and depositing and refilling of jhiri with watering & ramming and disposal of surplus excavated soil as directed with in a lead of 50 meter. All kind of soils	Cum	3430.00	111.60	382788.00
	Total (Rs.)				18993420.16

Executive Engineer (PHE-II)
JDA, Jaipur

Signature of Contractor